QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
	60		60	EA	TEMPORARY LETTER OR SYMBOL	646.690	1
	7 000		7 000	EA	LINE STRIPING TARGETS	646.76	EST
	226 000		226 000	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS (1)	646.85	56
	1		1	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I)	690.50	-
	1		1	EA	SPECIAL PROVISION (VIDEO VEHICLE DETECTION SYSTEM) (US 7 @ VT 7A/KOCHER DR.)	900.620	-
	1		1	EA	SPECIAL PROVISION (REMOVE AND REPLACE TRAFFIC SIGNAL CONTROLLER AND CABINET) (U.S. 7 @ VT 7A)	900.620	-
	1		1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.))	900.650	-
	50		50	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST
	2 600		2 600	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	59
	90		90	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	EST
					END ITEMS COMMON TO ALL ALTERNATES		
					BEGIN ALTERNATE A		
	655 000		655 000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	7353
					END ALTERNATE A		
					BEGIN ALTERNATE B		
	1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
	38 250		38 250	TON	SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR OR SBS POLYMER)	900.680	471
	5 100		5 100	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	EST
					END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		SPECIAL PROVISION (PAVER-PLACED SURFACE TREATMENT, TYPE C)
601 785	SY	MAINLINE
33 395	SY	INTERCHANGES
7 294	SY	BENNINGTON NORTH ST. HWY.
5 173	SY	SIDE ROADS
647 647	SY	SUBTOTAL
7 353	SY	ROUNDING
655 000	SY	TOTAL
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR OR SBS POLYMER)
35 104	TON	MAINLINE
1948	TON	INTERCHANGES
425	TON	BENNINGTON NORTH ST. HWY.
302	TON	SIDE ROADS
37 779	TON	SUBTOTAL
471	TON	ROUNDING
38 250	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

REVISION	BY	DATE
(1)	JLR	03/30/12

REVISED THE QUANTITY OF ITEM 646.85 REMOVAL OF EXISTING PAVEMENT MARKINGS FROM 452,000 SF TO 226,000 SF.

PROJECT NAME: BENNINGTON-MANCHESTER
PROJECT NUMBER: NH SURF (29)

FILE NAME: 11b026\11b026.dgn
PROJECT LEADER: FOWLER
DESIGNED BY: PVT. MGT.
IPARM FILE NAME: 11b026-9.i

PLOT DATE: 22-AUG-2013 14:3
DRAWN BY: PVT. MGT.
CHECKED BY: PAVT MGMT
SHEET 9 OF 63