6 INCH WHITE LINE

MM 4.155 ~ 4.196 LT (SOLID)(LANE LINE)(11' LT)
MM 4.155 ~ 4.435 LT (DASHED)
MM 4.155 ~ 4.196 LT (SOLID)(LANE LINE)(33' LT)
MM 4.196 ~ 4.238 LT (DOTTED)
MM 4.196 ~ 4.262 LT (DOTTED)
MM 4.155 ~ 4.470 LT (SOLID)
MM 4.155 ~ 4.363 RT (DASHED)
MM 4.155 ~ 4.470 RT (SOLID)

6 INCH YELLOW LINE

MM 4.155 ~ 4.340 CL (SOLID)(DBL)

LETTER OR SYMBOL

MM 4.157 LT (↰)
MM 4.157 LT (↱)
MM 4.166 LT (ONLY)
MM 4.166 LT (ONLY)
MM 4.175 LT (↱)
MM 4.175 LT (↰)
MM 4.185 LT (ONLY)
MM 4.185 LT (ONLY)
MM 4.196 LT (↰)
MM 4.196 LT (↱)
~~MM 4.363 RT (↗)~~
~~MM 4.397 RT (↗)~~ LANE DOES NOT END, TURNS INTO RAMP. LANE DROP NOT NEEDED.
MM 4.307 LT (AHEAD)(1 1' LT)
MM 4.307 LT (AHEAD)(22' LT)
MM 4.322 LT (SIGNAL)(1 1' LT)
MM 4.322 LT (SIGNAL)(22' LT)

24 INCH STOP BAR

MM 4.155 LT

COLD PLANED AT 1.5" DEPTH AND PAVED WITH 1.5" OF SUPERPAVE AND 0.75" OF PAVER PLACED SURFACE TREATMENT ON TOP

MM 4.196
END COLD PLANING
(FULL WIDTH)

STA. 235+22.40
MM 4.455
STOP PROJECT NH SURF(29)

7A NORTH SIDE DR.

STA. 219+38.40
MM 4.155

(MM 4.196)
(MM 4.238)
(MM 4.262)
(MM 4.315)

217'
350'
224'

4'
12'
11'
10'
33'
23'
8'

6" WHITE LINE
6" YELLOW LINE
ONLY
AHEAD
SIGNAL

BENNINGTON U.S. ROUTE 7
US 7 SOUTH
US 7 NORTH
EXISTING RAISED ISLAND

(MM 4.363)
(MM 4.435)

KOCHER DR.

MATCHLINE PREVIOUS SHEET

NOT TO SCALE

PAVING PROJECT LAYOUT #3

PROJECT NAME: BENNINGTON-MANCHESTER
PROJECT NUMBER: NH SURF(29)

FILE NAME: 11b026\11b026.dgn
PROJECT LEADER: M. FOWLER
DESIGNED BY: JLR
11b026-12.1

PLOT DATE: 22-AUG-2013 14:34
DRAWN BY: JLR
CHECKED BY: PVT. MGT.
SHEET 12 OF 63