QUANTITY SHEET 2

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES

RAILROAD	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		1		1	LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650	-
		1		1	LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC) (N.A.B.I.)	900.650	-
		1,950		1,950	SY	SPECIAL PROVISION (HAND-PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	EST
		50		50	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPARATION, TYPE I)	900.680	EST
		1,800		1,800	TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680	EST
		215		215	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683	EST
						END ITEMS COMMON TO ALL ALTERNATES		
						BEGIN ALTERNATE A		
		500,000		500,000	SY	SPECIAL PROVISION (PAVER PLACED SURFACE TREATMENT, TYPE C)	900.675	1,160
						END ALTERNATE A		
						BEGIN ALTERNATE B		
		1		1	LU	AIR VOIDS PAY ADJUSTMENT (N.A.B.I.)	490.31	-
		29,500		29,500	TON	SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT) (SBR OR SBS POLYMER)	900.680	400
		3,375		3,375	CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT) (RS-1H OR CRS-1H)	900.683	23
						END ALTERNATE B		

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS
		ALTERNATE A
		SPECIAL PROVISION (PAVER-PLACED SURFACE TREATMENT, TYPE C)
494,609	SY	MAINLINE
724	SY	BRIDGE 107 & APPROACHES
699	SY	BRIDGE 108 & APPROACHES
1,324	SY	BRIDGE 117 & APPROACHES
344	SY	BRIDGE 122 & APPROACHES
455	SY	BRIDGE 123 & APPROACHES
685	SY	TOWN HIGHWAYS & VT 102 & VT 18 APPROACHES
498,840	SY	SUBTOTAL
1,160	SY	ROUNDING
500,000	SY	TOTAL
		ALTERNATE B
		SPECIAL PROVISION (6.3 MM POLYMER MODIFIED BITUMINOUS CONCRETE PAVEMENT)(SBR OR SBS POLYMER)
28,852	TON	MAINLINE
43	TON	BRIDGE 107 & APPROACHES
41	TON	BRIDGE 108 & APPROACHES
77	TON	BRIDGE 117 & APPROACHES
20	TON	BRIDGE 122 & APPROACHES
27	TON	BRIDGE 123 & APPROACHES
40	TON	TOWN HIGHWAYS & VT 102 & VT 18 APPROACHES
29,100	TON	SUBTOTAL
400	TON	ROUNDING
29,500	TON	TOTAL

DETAILED SUMMARY OF QUANTITIES

QUANTITIES	UNIT	ITEMS

PROJECT NAME: ST. JOHNSBURY - GUILDHALL
PROJECT NUMBER: NH SURF (32)

FILE NAME: llb032\pllb032.dgn
PROJECT LEADER: FOWLER
DESIGNED BY: LOCKE
IPARM FILE NAME: pllb032_06.i

PLOT DATE: 03-FEB-2012
DRAWN BY: LOCKE
CHECKED BY: PAVT MGMT
SHEET 6 OF 22