

QUANTITY SHEET 1

STATE OF VERMONT
AGENCY OF TRANSPORTATION

SUMMARY OF ESTIMATED QUANTITIES								
RAILROAD	BRIDGE	ROADWAY	FULL C.E.	QUANTITIES GRAND TOTAL	UNIT	ITEMS	ITEM NO.	ROUNDING
		27,500		27,500	LF	BEGIN ITEMS COMMON TO ALL ALTERNATES		
						SHOULDER BERM REMOVAL	203.40	EST
		I		I	CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST
		5,150		5,150	SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10	55
		115,000		115,000	LF	MILLED RUMBLE STRIPS	213.10	EST
		2,350		2,350	TON	AGGREGATE SHOULDERS	402.12	70
		I		I	LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-
		70,000		70,000	LB	BITUMINOUS CRACK SEALING, "BLOW AND GO" METHOD (AASHTO M 324 (ASTM D 6690) TYPE II)	417.20	EST
	340			340	LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	3
	100			100	CF	RAPID SETTING CONCRETE REPAIR MATERIAL WITH COARSE AGGREGATE	580.20	EST
		130		130	HR	POWER BROOM RENTAL, TYPE I	608.30	EST
		400		400	HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST
		6,000		6,000	HR	FLAGGERS	630.15	EST
			I	I	LS	FIELD OFFICE, ENGINEERS	631.10	-
			I	I	LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-
			3,000	3,000	DL	FIELD OFFICE, TELEPHONE (N.A.B.I.)	631.26	-
			I	I	LS	MOBILIZATION/DEMOBILIZATION	635.11	-
			I	I	LS	TRAFFIC CONTROL	641.10	-
		3		3	EA	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-
		546,260		546,260	LF	4 INCH WHITE LINE	646.20	EST
		475,720		475,720	LF	4 INCH YELLOW LINE	646.21	EST
		520		520	LF	8 INCH WHITE LINE	646.22	EST
		130		130	LF	8 INCH YELLOW LINE	646.23	EST
		70		70	LF	24 INCH STOP BAR	646.26	EST
		50		50	EA	LETTER OR SYMBOL	646.30	-
		144		144	LF	CROSSWALK MARKING	646.31	EST
		273,130		273,130	LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	EST
		237,860		237,860	LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	EST
		260		260	LF	TEMPORARY 8 INCH WHITE LINE, PAINT	646.642	EST
		65		65	LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	EST
		35		35	LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	EST
		25		25	EA	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-
		72		72	LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	-
		10,260		10,260	EA	LINE STRIPING TARGETS	646.76	EST
		170,330		170,330	SF	REMOVAL OF EXISTING PAVEMENT MARKINGS	646.85	EST
		40		40	SF	TRAFFIC SIGNS, TYPE A	675.20	3
		60		60	LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	EST
		I		I	LU	PRICE ADJUSTMENT, FUEL (N.A.B.I)	690.50	-

[illegible][illegible]