

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
							ROADWAY	EROSION CONTROL	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1			1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			ITEM 900.645 SPECIAL PROVISION (TEMPORARY ROADWAY WIDENING)(WORK ZONE)
							1			1		ACRE	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.11	0.1			
							825			825		CY	COMMON EXCAVATION	203.15	28			INSTALLING TWO-WAY TEMPORARY TRAFFIC PHASING
							100			100		CY	SOLID ROCK EXCAVATION	203.16	EST.			55 CY SUBBASE OF DENSE GRADED CRUSHED STONE
							1			1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	-			2000 LF TEMPORARY 4 INCH WHITE LINE, TEMPORARY MARKING TAPE
							20			20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			2000 LF TEMPORARY 4 INCH YELLOW LINE, TEMPORARY MARKING TAPE
							30			30		HR	POWER BROOM RENTAL, TYPE II	608.31	EST.			500 SY GEOTEXTILE UNDER STONE FILL
							20			20		HR	TRUCK RENTAL	608.37	EST.			2 EA REMOVAL OF EXISTING DELINEATOR
							3			3		EACH	ENERGY ABSORPTION ATTENUATOR	621.56	-			52 TON BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY
							287.5			287.5		LF	REMOVE AND RESET GUARDRAIL	621.75	-			REMOVAL OF TWO-WAY TEMPORARY TRAFFIC PHASING
							840			840		LF	TEMPORARY TRAFFIC BARRIER	621.90	10			
							360			360		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.			
							300			300		HR	FLAGGERS	630.15	EST.			
									1	1		LS	FIELD OFFICE, ENGINEERS	631.10	-			
									1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
									3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
							1			1		LS	MOBILIZATION/DEMOBILIZATION	635.11	-			
							1			1		LS	TRAFFIC CONTROL	641.10	-			
							2			2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
								100		100		SY	GEOTEXTILE FOR SILT FENCE	649.51	10			
								150		150		LB	SEED	651.15	30			
								1025		1025		LB	FERTILIZER	651.18	25			
								4		4		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
								4		4		TON	HAY MULCH	651.25	EST.			
							550			550		CY	TOPSOIL	651.35	12			
								1		1		LS	EPSC PLAN	652.10	-			
								15		15		HR	MONITORING EPSC PLAN	652.20	EST.			
								1		1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30	-			
								3050		3050		SY	TEMPORARY EROSION MATTING	653.20	66			
								5		5		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	EST.			
								40		40		CY	VEHICLE TRACKING PAD	653.35	4			
								2		2		EACH	INLET PROTECTION DEVICE, TYPE I	653.40	-			
								1040		1040		LF	PROJECT DEMARCATION FENCE	653.55	28			
							2			2		EACH	DELINEATOR WITH STEEL POST	676.10	-			
								5		5		EACH	REMOVE AND REPLACE REFLECTOR UNIT	676.15	EST.			
							100			100		CY	SPECIAL PROVISION (REMOVAL OF LEDGE SALVAGE MATERIAL)	900.608	EST.			
							400			400		CY	SPECIAL PROVISION (REMOVAL OF LEDGE WASTE MATERIAL)	900.608	EST.			
							20			20		CY	SPECIAL PROVISION (TRIM BLASTING, TRUCK MEASUREMENT)	900.608	EST.			
							100			100		HR	SPECIAL PROVISION (HAND SCALING)	900.630	EST.			
							50			50		HR	SPECIAL PROVISION (MACHINE SCALING)	900.630	EST.			

PROJECT NAME: TOWNSHEND  
PROJECT NUMBER: STP 015-1(22)

FILE NAME: d1b050frm.dgn  
PROJECT LEADER: K. UPMAL  
DESIGNED BY: C. LEACH  
QUANTITY SHEET 1

PLOT DATE: 1/9/2015  
DRAWN BY: C. LEACH  
CHECKED BY: B. KIPP  
SHEET 6 OF 34