STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 3

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 2.0 2.16	SQUARE STEEL (in) lb/ft 2.0 2.42	SQUARE STEEL (in) lb/ft 2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 1.7	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 3.0 7.6	TUBULAR STEEL Ø (in) lb/ft 3.5 9.0	TUBULAR STEEL Ø (in) lb/ft 4.0 10.8	TUBULAR STEEL Ø (in) lb/ft 5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
												OPTION ITEMS																							
12	89 NORTH RAMP CLOSED DO NOT STOP OR TURN	1	89.7	48.0	29.90																													62	
13	89 SOUTH White River Junction; COVER SIGN 89 NORTH Burlington		210.0	96.0																													COVER OVERHEAD SIGN: I-89 NORTH BURLINGTON		
14	DETOUR NORTH 89	1	24.0	12.0	2.00																												M4-8	SHSM	
		1	24.0	12.0	2.00																												M3-1 (INTERSTATE)	SHSM	
		1	24.0	24.0	4.00																												M1-1	SHSM	
		1	21.0	15.0	2.19																												M6-3 (INTERSTATE)	SHSM	
15		1	21.0	15.0	2.19																												M6-3	SHSM	
	SOUTH	1	24.0	12.0	2.00																												M3-3 (INTERSTATE)	SHSM	
		1	21.0	15.0	2.19																												M6-3 (INTERSTATE)	SHSM	
	DETOUR NORTH 89	1	24.0	12.0	2.00																												M4-8	SHSM	
		1	24.0	12.0	2.00																												M3-1 (INTERSTATE)	SHSM	
		1	24.0	24.0	4.00																												M1-1	SHSM	
		1	21.0	15.0	2.19																												M6-1 (INTERSTATE)	SHSM	
16	89 NORTH RAMP CLOSED	1	56.6	48.0	18.87																													62	
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB								
				SHEET TOTALS	SF 45.63	SF 29.90	EA	SF				FT			FT					LB			EA	LB				EA	EA	LB					

SHSM = 2004 FHWA STANDARD HIGHWAY SIGNS & MARKINGS & 2012 SUPP.
FYG = FLUORESCENT YELLOW GREEN

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE TRAFFIC & SAFETY DIVISION'S "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: MONTPELIER
PROJECT NUMBER: NH 028-2(9)

FILE NAME: dllb066trf.dgn
PROJECT LEADER: P. PELOQUIN
DESIGNED BY: P. PELOQUIN
TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 24-MAY-2013
DRAWN BY: P. PELOQUIN
CHECKED BY: A. BOMBARDIER
SHEET 58 OF 62