

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES											TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						4					4		EACH	GUARDRAIL APPROACH SECTION TO CONCRETE BRIDGE RAILING, TL-3	621.747				
						163					163		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						200					200		HR	FLAGGERS	630.15				
										1	1		LS	FIELD OFFICE, ENGINEERS	631.10				
										1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
										1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										3000	3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							520				520		HR	EMPLOYEE TRAINEESHIP	634.10				
						1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1605					1605		LF	4 INCH WHITE LINE	646.20				
						1490					1490		LF	4 INCH YELLOW LINE	646.21				
											2300		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								300			300		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
								100			100		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
								40			40		LB	SEED	651.15				
								300			300		LB	FERTILIZER	651.18				
								2			2		TON	AGRICULTURAL LIMESTONE	651.20				
								2			2		TON	HAY MULCH	651.25				
								125			125		CY	TOPSOIL	651.35				
								500			500		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN	652.10				
								15			15		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
								700			700		SY	TEMPORARY EROSION MATTING	653.20				
								60			60		CY	VEHICLE TRACKING PAD	653.35				
								1			1		EACH	FILTER BAG	653.45				
								400			400		LF	BARRIER FENCE	653.50				
								1000			1000		LF	PROJECT DEMARCATION FENCE	653.55				
						6.91					6.91		SF	TRAFFIC SIGNS, TYPE A	675.20				
						44					44		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						2					2		EACH	REMOVING SIGNS	675.50				
						2					2		EACH	ERECTING SALVAGED SIGNS	675.60				
										1	1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
										33	33		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A HIGH STRENGTH)	900.608				
										240	240		LF	SPECIAL PROVISION (OBSTRUCTION REMOVAL FOR DRIVING PILES)	900.640				
										1	1		LS	SPECIAL PROVISION (POST-TENSIONING, PIER CAP)	900.645				
										1	1		LS	SPECIAL PROVISION (POST-TENSIONING, PIER SUB-CAP)	900.645				
						1					1		LS	SPECIAL PROVISION (REMOVAL OF TEMPORARY BRIDGE AND APPROACHES)	900.645				
						1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)	900.645				
						1					1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				

PROJECT NAME: JAMAICA
PROJECT NUMBER: ER BRF 013-1(16)

FILE NAME: s1lb212quantitysheet.dgn
PROJECT LEADER: K. HIGGINS
DESIGNED BY: G. LAROCHE
QUANTITY SHEET 2

PLOT DATE: 23-OCT-2012
DRAWN BY: G. LAROCHE
CHECKED BY: K. FRIEDLAND
SHEET 5 OF 85