



BILL OF MATERIAL										
Mark	Qty.	Description	SH	Length	Remark	ABM	Total Weight	Seq	Qty	
			Grd						/Seq	
103G1	ONE	GIRDER				16629	16809	1	1	
103G1	1	GIRDER		78-5 11/16						
TF103	1	PL1x16	A70950WT2	78-4 7/16		100-1	4267			
W103	1	PL1/2x52	A70950WT2	78-5 11/16		100-2	6943			
BF103	1	PL1x16	A70950WT2	78-4 3/16		100-1	4266			
x101b	2	PL7/8x7 1/2	A70950WT2	4-4 WB		101-1	194			
x101c	12	PL1/2x7 1/2	A70950WT2	4-4		101-2/3	664			
x101spa	2	PL1/2x16	A70950WT2	2-2 1/4		102-1	52			
x101spb	2	PL1/2x7	A70950WT2	2-2 1/4		102-2	52			
x101spc	2	PL1/2x43	A70950WT2	8 1/4		102-3	101			
x101spd	2	PL1/2x7	A70950WT2	2-8 1/4		102-4	64			
x101spe	1	PL1/2x16	A70950WT2	2-8 1/4		102-5	73			
FB		FIELD BOLTS								
78F3	84	.7/8 Dia A325 TYP3		3 1/2	1FL WASH		67			
78F312	72	.7/8 Dia A325 TYP3		3 1/2	1FL WASH		58			

GENERAL NOTES: SEE GN100
 HOLES: 15/16 (U.N.)
 CLEANING AND PAINTING: SEE SHEET P100 AND P101

See standard specification 506.24(a)(9), no payment will be made for bolts, nuts, washers, they are considered to be incidental

609

Vermont Agency of Transportation
RECEIVED
 CK'D BY M.E.M. OK'D BY C.W.M.
 July 09, 2012
 RESUBMIT APPROVED AS NOTED
 BY C. CARLSON DATE 07-27-2012

No	REVISION	DATE	PAR	EG
		07/06/12	BR	EG

NOTE: BOLT 1 WASHER: 1 WASHER UNDER NUT U.N.
 BOLT 2 WASHER: 1 WASHER UNDER HEAD U.N.
 1 WASHER UNDER HEAD U.N.

STRUCTURAL
 Bridges
 a division of
CANAM
 385 River Road, Claremont,
 NH 03743
 Tel:(603) 542-5202 Fax:(603) 542-5312

PROJECT: VT RT 9, BRIDGE NO. 11
 TOWN OF WOODFORD, VT
 OVER WALDOOMSAC RIVER

TITLE: GIRDER 103G1

REFERENCE: PROJECT NO. ER BHF 010-1 (44)

DATE	BY	DATE	BY	DATE	BY
BR	JULY 2012	UN04260			
GG	JULY 2012	103-2 A			

BF 103
 BF 102
 web 9'