

BR52 QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (VT 30 - BRIDGE NO. 52)	201.10				
						680				680		CY	COMMON EXCAVATION	203.15				
								140		140		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
						0.5				0.5		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
								920		920		CY	STRUCTURE EXCAVATION	204.25				
								490		490		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
						1290				1290		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
						490				490		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
						15				15		CWT	EMULSIFIED ASPHALT	404.65				
						0.5				0.5		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								5		5		GAL	WATER REPELLENT, SILANE	514.10				
								170		170		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
								1		1		EACH	REMOVAL OF STRUCTURE (2 EA. 72" DIA. CGMP)	529.15				
								1		1		LS	PRECAST CONCRETE STRUCTURE (12'-0" X 7'-0" X 72'-0" BOX)	540.10				
						0.5				0.5		MGAL	DUST CONTROL WITH WATER	609.10				
						0.5				0.5		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
								110		110		CY	STONE FILL, TYPE II	613.11				
						329				329		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
						3				3		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						300				300		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
								130		130		TON	CRUSHED STONE BEDDING	629.54				
						10				10		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						80				80		HR	FLAGGERS	630.15				
									0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
									0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						0.5				0.5		LS	MOBILIZATION/DEMobilIZATION	635.11				
						1150				1150		LF	DURABLE 4 INCH WHITE LINE	646.400				
						680				680		LF	DURABLE 4 INCH YELLOWLINE	646.410				
								60		60		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
								270		270		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							60			60		SY	GEOTEXTILE FOR SILT FENCE	649.51				
						10				10		LB	SEED	651.15				
						60				60		LB	FERTILIZER	651.18				
						1				1		TON	AGRICULTURAL LIMESTONE	651.20				
						1				1		TON	HAY MULCH	651.25				
						40				40		CY	TOPSOIL	651.35				
						140				140		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN (VT 30 - BRIDGE NO. 52)	652.10				
							40			40		HR	MONITORING EPSC PLAN	652.20				

PROJECT NAME: WINHALL
 PROJECT NUMBER: STP CULV(3I)
 FILE NAME: z1lb268frm.dgn
 PROJECT LEADER: M. CHENETTE
 DESIGNED BY: J. HUNGERFORD
 BR52 QUANTITY SHEET 1
 PLOT DATE: 9/25/2014
 DRAWN BY: L. BUXTON
 CHECKED BY: J. HUNGERFORD
 SHEET 9 OF 60

