

## BR52 QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (VT 30 - BRIDGE NO. 52)	652.30				
								590			590		SY	TEMPORARY EROSION MATTING	653.20				
								10			10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								2			2		EACH	FILTER BAG	653.45				
								530			530		LF	PROJECT DEMARCATION FENCE	653.55				
							1				1		SF	TRAFFIC SIGNS, TYPE A	675.20				
							30				30		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							0.5				0.5		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
									130		130		CY	SPECIAL PROVISION (STONE FILL, CULVERT LINING)	900.608				
									1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM) (VT 30 - BRIDGE NO. 52)	900.645				
							1				1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (VT 30 - BRIDGE NO. 52)	900.645				
							1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
							1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
							630				630		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: WINHALL  
 PROJECT NUMBER: STP CULV(3I)  
 FILE NAME: z1lb268frm.dgn  
 PROJECT LEADER: M. CHENETTE  
 DESIGNED BY: J. HUNGERFORD  
 BR52 QUANTITY SHEET 2

PLOT DATE: 9/25/2014  
 DRAWN BY: L. BUXTON  
 CHECKED BY: M. CHENETTE  
 SHEET 10 OF 60

