

QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	TRAINING	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					1					1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10	-			
					521			6710		7231		CY	COMMON EXCAVATION	203.15	ROUND			
					20			230		250		CY	SOLID ROCK EXCAVATION	203.16	EST.			
								5760		5760		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27	ROUND			
					1					1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22	EST.			
								620		620		CY	STRUCTURE EXCAVATION	204.25	ROUND			
								340		340		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30	ROUND			
					425					425		SY	COLD PLANING-BIT.PAVEMENT	210.10	ROUND			
					310					310		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35	ROUND			
					5.1					5.1		CWT	EMULSIFIED ASPHALT	404.65	ROUND			
					1					1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50	-			
								188		188		CY	CONCRETE, HIGH PERFORMANCE CLASS A	501.33	ROUND			
								138		138		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34	ROUND			
								1		1		LS	FURNISHING EQUIPMENT FOR DRIVING PILING	504.10	-			
								240		240		LF	STEEL PILING, HP 12 X 74	505.16	ROUND			
								2		2		EACH	DYNAMIC PILE LOADING TEST	505.45	-			
								168000		168000		LB	STRUCTURAL STEEL, PLATE GIRDER	506.55	ROUND			
								8120		8120		LB	REINFORCING STEEL, LEVEL I	507.11	ROUND			
								37190		37190		LB	REINFORCING STEEL, LEVEL II	507.12	ROUND			
								1		1		LS	SHEAR CONNECTORS (1630 - 7/8" X 7")	508.15				
								517		517		SY	LONGITUDINAL DECK GROOVING	509.10	ROUND			
								55		55		GAL	WATER REPELLENT, SILANE	514.10	ROUND			
								76		76		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	516.10	ROUND			
								76		76		LF	JOINT SEALER, HOT POURED	524.11	ROUND			
								259		259		LF	BRIDGE RAILING, GALVANIZED 2 RAIL BOX BEAM	525.33	ROUND			
								1		1		EACH	REMOVAL OF STRUCTURE (15' DIAMETER X 182' CMPP)	529.15				
								10		10		EACH	BEARING DEVICE ASSEMBLY, PLAIN ELASTOMERIC PAD	531.16	-			
							20			20		HR	POWER GRADER RENTAL	608.15	EST.			
							20			20		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25	EST.			
							20			20		HR	TRUCK RENTAL	608.37	EST.			
							20			20		HR	LOADER RENTAL, TYPE I	608.40	EST.			
					45					45		MGAL	DUST CONTROL WITH WATER	609.10	ROUND			
							5			5		CY	STONE FILL, TYPE I	613.10	ROUND			
								750		750		CY	STONE FILL, TYPE II	613.11	ROUND			
								1850		1850		CY	STONE FILL, TYPE IV	613.13	ROUND			
					160					160		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28	-			
					476.5					476.5		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	-			
					2					2		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50	-			
					3					3		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-			
					4					4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM	621.72	-			

PROJECT NAME: **HYDE PARK**
 PROJECT NUMBER: **STP CULV(26)**
 FILE NAME: z11b292.xls PLOT DATE: 11/06/2013
 PROJECT LEADER: R. HEBERT DRAWN BY: S. MORGAN
 DESIGNED BY: D. MYERS CHECKED BY: J. OLUND
 QUANTITY SHEET #1 SHEET 6 OF 60

