ITEM DETAIL SUMMARY SHEET 6

LOCATION			MISCELLANEOUS														REMARKS
			617.10	617.12	618.10	618.30	619.17	649.31	651.40	653.20	676.10						
BEGIN MILE STA.	END MILE STA.	POS.	RELOCATE MAILBOX, SINGLE SUPP.	RELOCATE MAILBOX, MULTIPLE SUPP.	PORTLAND CEMENT CONC. S.W., 5 INCH	DETECTABLE WARNING SURFACE	YIELDING MARKER POSTS	GEOTEXTILE UNDER STONE FILL	GRUBBING MATERIAL	TEMPORARY EROSION MATTING	DELINEATOR WITH STEEL POST						
			EA	EA	SY	SF	EACH	SY	SY	SY	EACH						
TOWN OF RICHFORD																	
SNTH 139 (CONT.)																	
19+00		RT			4	14											CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE
19+01		LT			2	8											CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE
20+94		LT			2	6											CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE
21+16		RT			2	6											CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE
21+28		LT			2	6											CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE
21+29	25+82	LT															CONSTRUCT BITUMINOUS GUTTER BETWEEN SHOULDER AND FRONT OF SIDEWALK, SEE DETAIL ON SHEET 18.
21+45		RT			5	6											CONSTRUCT SIDEWALK RAMP, TYPE I
25+87		LT			2	6											CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE
26+27		LT			4	12											CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE
27+67		LT			4	6											CONSTRUCT SIDEWALK RAMP, TYPE I
28+13		LT			5	6											CONSTRUCT SIDEWALK RAMP, TYPE I
32+52		LT			2	8											CONSTRUCT SIDEWALK RAMP, TYPE I
33+15		LT			2	8											CONSTRUCT SIDEWALK RAMP, TYPE I
43+81		LT			5	6											CONSTRUCT SIDEWALK RAMP, TYPE I
44+58		LT			7	6											CONSTRUCT SIDEWALK RAMP, TYPE I
92+62.0	95+67.5	LT								50	2						INSTALL ANCHOR @ STA. 92+62.0 & STA. 95+67.5. REFER TO REDUCED POST SPACING DETAIL ON SHEET 18.
SHEET 10 SUBTOTALS:			11	1	139	174	15	2166	-	983	4						
SHEET 12 SUBTOTALS:			1	-	178	284	14	1266	218	433	1						
SHEET 14 SUBTOTALS:			-	-	48	104	-	-	-	50	2						
SUBTOTALS			12	-	365	562	29	3432	-	1466	7						
ROUNDING			-	-	5	8	-	18	7	34	-						
TOTALS			12	1	370	570	29	3450	225	1500	7						

ITEM DETAIL SUMMARY SHEET #6

PROJECT NAME: ENOSBURG - RICHFORD
PROJECT NUMBER: STP 2939(I)

FILE NAME: p11b312.dgn
PROJECT LEADER: J. LITTLE
DESIGNED BY: J. LITTLE
IPARM FILE: p11b312idss06.i

PLOT DATE: 3/19/2014
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 14 OF 115