STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 07

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT ROUTE 108 ENOSBURG (CONT.)																																				
248+00, RT	Richford 10 → St. Albans 18 → NORTH TO VERMONT 108 VERMONT 105	1	72	12	6.00						2												14.25 13.25 2	X									VDI-1a VDI-1a M3-1 (GREEN ON WHITE) (GREEN ON WHITE) M5-1 (GREEN ON WHITE) M4-5 (GREEN ON WHITE) (GREEN ON WHITE) M5-1 (GREEN ON WHITE)		107 107 	 E-136B E-136B E-136B E-136B E-136B E-136B
		1	72	12	6.00																															
		1	24	12	2.00																															
		1	30	24	5.00																															
		1	21	15	2.19																															
		1	24	12	2.00																															
		1	30	24	5.00																															
		1	21	15	2.19																															
248+47, LT	W Enosburg Rd Duffy Hill Rd STOP B-B 1080 0603 0471	1	42	8	2.35						13.75 1						X	X																D3-1 D3-1 RI-1 VD-700	 X 	105 105 	 E-138
		1	36	8	2.01																															
		1	30	30	6.25																															
		1	6	10	0.42																															
250+00, RT		1	30	30	6.25						15 1					X		X															W3-1 VD-701	X 	 110	
	BRIDGE 50 VT 108	1	6	10	0.42																															
252+72, RT	STOP ALL WAY B-B 1080 0603 0480	1	30	30	6.25						13.75 1					X		X															RI-1 RI-3P VD-700	X X 	 	 E-138
		1	18	6	0.75																															
		1	6	10	0.42																															
252+80, LT	BRIDGE 50 VT 108	1	6	10	0.42						6.75 1				X			X															VD-701		110	
252+92, LT	STOP ALL WAY	1	30	30	6.25						14 1					X		X															RI-1 RI-3P	X X	 	
		1	18	6	0.75																															
253+18, LT	NO OUTLET	1	30	30	6.25						14 1					X		X															WI4-2	X		
TOTALS					SF 69.17	SF	EA.	SF				FT	FT	FT	FT 10	FT 57	FT 14		EA	LB	LB	LB	EA. 2	LB 187	LB	LB	LB	EA.	EA.	LB						

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #7

PROJECT NAME: ENOSBURG-RICHFORD
PROJECT NUMBER: STP 2939(I)

FILE NAME: p11b312.dgn
PROJECT LEADER: J. LITTLE
DESIGNED BY: J. LITTLE
IPARM FILE: p11b312tss07.i
PLOT DATE: 3/19/2014
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 79 OF 115