STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 10

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75 1.88	2.0 2.42	2.5 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 1.3	4.0 1.7	4.0 MOD 1.7	TUBULAR STEEL Ø (in) FOUND-ATION	3.0 7.6	3.5 9.0	4.0 10.8	5.0 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT ROUTE 108 ENOSBURG (CONT.)																																				
262+27, LT		1	30	30	6.25						14.25 1					X		X															W3-1	X		
264+50, RT	SPEED LIMIT 35 1080 0603 0501	1 1	24 6	30 10	5.00 0.42						15 1					X		X															R2-1 VD-700	X		 E-138
264+50, LT	SPEED LIMIT 25	1	24	30	5.00						13.25 1					X		X															R2-1	X		
265+56, LT	← Richford 10 Bakersfield 9 → St. Albans 18 →	1 1 1	72 72 72	12 12 12	6.00 6.00 6.00						10 10 2						X	X															VDI-1a VDI-1a VDI-1a	USE SOIL BEARING SLIP BASES. PAID AS ITEM 900.620 SPECIAL PROVISION (SOIL BEARING SLIP BASE) (2½")		107 107 107	
266+50, RT	↑ West Berkshire 6 ↑ Canada Border 8	1 1	72 72	12 12	6.00 6.00						14.25 12 2					X		X															VDI-1a VDI-1a		107 107	
267+00, LT	JCT VERMONT 105	1 1	21 30	15 24	2.19 5.00						13.50 1					X		X															M2-1 (GREEN ON WHITE) (GREEN ON WHITE)			E-136B E-136B
268+00, LT	WINTER PARKING BAN DEC. 1ST THRU APRIL 1ST MIDNIGHT TO 6 AM						1				11.75 1					X		X																		
269+00, RT	BRIDGE 51 VT 108	1	6	10	0.42						7.75 1				X			X															VD-701		110	
269+50, LT	BRIDGE 51 VT 108 1080 0603 0510	1 1	6 6	10 10	0.42 0.42						7.50 1				X			X															VD-701 VD-700		110	 E-138
TOTALS			SF 55.12	SF	EA. 1	SF						FT	FT	FT	FT 19	FT 106	FT 31		EA	LB	LB	LB		LB	LB	LB	LB	EA.	EA.	LB					

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #10

PROJECT NAME: ENOSBURG-RICHFORD
PROJECT NUMBER: STP 2939(1)

FILE NAME: p11b312.dgn
PROJECT LEADER: J. LITTLE
DESIGNED BY: J. LITTLE
IPARM FILE: p11b312tss10.i

PLOT DATE: 3/19/2014
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 82 OF 115