STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	SIGN DIMENSIONS WIDTH (in)	SIGN DIMENSIONS HEIGHT (in)	NEW & SALVAGED SIGNS "A"	NEW & SALVAGED SIGNS "B"	NEW & SALVAGED SIGNS SALV SIGN	NEW & SALVAGED SIGNS SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	FLANGED CHANNEL lb/ft 2.0	FLANGED CHANNEL lb/ft 3.0	SQUARE STEEL (in) lb/ft 1.75 (1.88)	SQUARE STEEL (in) lb/ft 2.0 (2.42)	SQUARE STEEL (in) lb/ft 2.5 (3.35)	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0 (1.3)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 (1.7)	TUBULAR ALUMINUM Ø (in) lb/ft 4.0 MOD (1.7)	TUBULAR STEEL Ø (in) FOUNDATION	TUBULAR STEEL Ø (in) lb/ft 3.0 (7.6)	TUBULAR STEEL Ø (in) lb/ft 3.5 (9.0)	TUBULAR STEEL Ø (in) lb/ft 4.0 (10.8)	TUBULAR STEEL Ø (in) lb/ft 5.0 (14.6)	W-SHAPE STEEL FTG. SIZE 24"	W-SHAPE STEEL FTG. SIZE 30"	W-SHAPE STEEL WEIGHT	W-SHAPE STEEL POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	SIGN DETAIL DETAIL ON SHEET NUMBER	SIGN DETAIL STD. SHEET NUMBER
VT ROUTE 108 ENOSBURG (CONT.)																																				
286+14, RT	1080 0603 0542	1	12	36	3.00						11					X		X															OM3-R	X		
		1	6	10	0.42						1																						VD-700			E-138
286+14, LT		1	12	36	3.00						10.75 1					X		X															OM3-L	X		
286+28, RT		1	12	36	3.00						11.50 1					X		X															OM3-L	X		
286+31, LT		1	12	36	3.00						10.75 1					X		X															OM3-R	X		
288+00, LT	YOU CAN'T DWI AFFORD IT						1				13.75 1					X		X																		
311+63, RT	Berkshire Enosburg	1	72	10	5.00						14.75																						VD-024		III	
	STATE HIGHWAY BEGINS	1	6	10	0.42						15																						VD-700			E-138
	SPEED LIMIT 50	1	24	18	3.00						2						X	X															VR-039			E-141
		1	24	30	5.00																												R2-1	X		
	1080 0602 0000 / 1080 0603 0590	1	6	10	0.42																												VD-700			E-138
311+63, LT	STATE HIGHWAY ENDS / SPEED LIMIT 35	1	24	18	3.00						15.50 1						X	X															VR-038			E-141
		1	30	36	7.50																												R2-1	X		
TOTALS					SF 36.76	SF	EA. 1	SF				FT	FT	FT	FT	FT 62	FT 33		EA	LB	LB	LB		LB	LB	LB	LB	EA.	EA.	LB					
												FT			FT 95					LB			EA.	LB											

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

USE SOIL BEARING SLIP BASES. PAID AS ITEM 900.620 SPECIAL PROVISION (SOIL BEARING SLIP BASE) (2½")

TRAFFIC SIGN SUMMARY SHEET #11

PROJECT NAME: ENOSBURG-RICHFORD
PROJECT NUMBER: STP 2939(1)

FILE NAME: p11b312.dgn
PROJECT LEADER: J. LITTLE
DESIGNED BY: J. LITTLE
IPARM FILE: p11b312tss11.i
PLOT DATE: 3/19/2014
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 83 OF 115