STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 21

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (in) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
VT ROUTE 105 RICHFORD (CONT.)																																				
133+53, RT	STATE HIGHWAY BEGINS	1	24	18	3.00						14.25																						VR-039			E-141
	SPEED LIMIT 50	1	24	30	5.00						1					X		X															R2-1	X		
	1050 0611 0253	1	6	10	0.42																												VD-700			E-138
133+53, LT	STATE HIGHWAY ENDS	1	24	18	3.00						16.75																						VR-038			E-141
	SPEED LIMIT 35	1	30	36	7.50						1						X	X															R2-1	X		
SNTH 139 RICHFORD																																				
1+14, LT	BIKE ROUTE	1	24	18	3.00						13																						DI1-1	X		
		1	12	9	0.75						1					X		X															M6-1 (WHITE ON GREEN)	X		
1+40, LT	Intervale Ave	1	42	8	2.35						13.25																						D3-1		106	
	Main St	1	24	8	1.34						1						X	X															D3-1		105	
	STOP B-B	1	30	30	6.25																												R1-1	X		
	1390 0611 0003	1	6	10	0.42																												VD-700			E-138
1+91, LT	DOG WASTE						1				12 1					X		X																		
4+00, LT	E. Berkshire 5	1	72	12	6.00																												VDI-1a		108	
	Enosburg Falls 10	1	72	12	6.00																		15.75 14										VDI-1a		108	
	North Troy 19	1	72	12	6.00																												VDI-1a		108	
	EAST / WEST	1	24	12	2.00						2												2	X									M3-2 (GREEN ON WHITE)	X		
	VERMONT 105 / VERMONT 105	1	30	24	5.00																												(GREEN ON WHITE)			E-136B
		1	21	15	2.19																												M6-1 (GREEN ON WHITE)	X		
		1	24	12	2.00																												M3-4 (GREEN ON WHITE)	X		
		1	30	24	5.00																												(GREEN ON WHITE)			E-136B
		1	21	15	2.19																												M6-3 (GREEN ON WHITE)	X		
												FT	FT	FT	FT	FT 40	FT 29		EA	LB	LB	LB		LB 203	LB	LB	LB								
TOTALS					SF 69.41	SF	EA. 1	SF				FT			FT 69					LB			EA. 2	LB 203				EA.	EA.	LB					

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #21

PROJECT NAME: ENOSBURG-RICHFORD
PROJECT NUMBER: STP 2939(1)

FILE NAME: p11b312.dgn
PROJECT LEADER: J. LITTLE
DESIGNED BY: J. LITTLE
IPARM FILE: p11b312tss21.i

PLOT DATE: 3/19/2014
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 93 OF 115