STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 24

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) 1.75 lb/ft 1.88	2.0 lb/ft 2.42	2.5 lb/ft 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) 3.0 lb/ft 1.3	4.0 lb/ft 1.7	4.0 MOD lb/ft 1.7	TUBULAR STEEL Ø (In) FOUNDATION	3.0 lb/ft 7.6	3.5 lb/ft 9.0	4.0 lb/ft 10.8	5.0 lb/ft 14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
SNTH 139 RICHFORD (CONT.)																																				
I3+00, RT	BRIDGE 41 VT 139	1	30	30	6.25						13.75 1					X		X															W3-1	X		
		1	6	10	0.42																												VD-701		110	
I4+65, LT	BRIDGE 41 VT 139	1	6	10	0.42						6.50 1				X			X	1													VD-701 SLEEVE TO BE INSTALLED IN EXISTING SIDEWALK PER VAOT STANDARD T-45		110	
I4+92, RT	STOP ALL WAY	1	30	30	6.25						14 1					X		X	1													RI-1 SLEEVE TO BE INSTALLED IN EXISTING SIDEWALK PER VAOT STANDARD T-45	X		
		1	18	6	0.75																											RI-3P	X		
I4+97, LT	STOP ALL WAY 1390 0611 0028 B-B	1	30	30	6.25						13.25 1					X		X															RI-1	X		
		1	18	6	0.75																												RI-3P USE EXISTING SLEEVE	X		
		1	6	10	0.42																												VD-700			E-138
I5+45, LT	E. Berkshire 5 / North Troy 19 / SOUTH TO VERMONT 139 105 / BIKE ROUTE	1	72	12	6.00						15.25 15.50 2												SEE DWR 9/23/14 SLIP BASE 2 ~~2~~	X									VDI-1a		108	
		1	72	12	6.00																												VDI-1a		108	
		1	24	12	2.00																												M3-3 (BLACK ON WHITE)	X		
		1	30	24	5.00																												MI-5	X		
		1	21	15	2.19																												M6-1 (BLACK ON WHITE)	X		
		1	24	12	2.00																												M4-5 (GREEN ON WHITE)	X		
		1	30	24	5.00																												(GREEN ON WHITE)			E-136B
		1	21	15	2.19																												M6-1 (GREEN ON WHITE)	X		
		1	24	18	3.00																												DII-1	X		
		1	12	9	0.75																												M6-1 (GREEN ON WHITE)	X		
I5+45, LT	Town St / River St / STOP / ALL WAY / ONE WAY 1390 0611 0030 B-B	1	30	8	1.68						15 1					X		X															D3-1		106	
		1	30	8	1.68																												D3-1		106	
		1	30	30	6.25																												RI-1	X		
		1	18	6	0.75																												RI-3P	X		
		1	36	12	3.00																												R6-1 INSTALL 90 DEGREES TO SIGN RI-1	X		
		1	6	10	0.42																												VD-700			E-138
TOTALS					SF 69.42	SF	EA.	SF				FT	FT	FT	FT 8	FT 55	FT 63		EA 2	LB	LB	LB	EA. 2	LB 221	LB	LB	LB	EA.	EA.	LB						

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #24

PROJECT NAME: ENOSBURG-RICHFORD
PROJECT NUMBER: STP 2939(I)

FILE NAME: p11b312.dgn
PROJECT LEADER: J. LITTLE
DESIGNED BY: J. LITTLE
IPARM FILE: p11b312tss24.i
PLOT DATE: 3/19/2014
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 96 OF 115