STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 25

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (In)	HEIGHT (In)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (In) lb/ft 1.75	2.0	2.5	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (In) lb/ft 3.0	4.0	4.0 MOD	TUBULAR STEEL Ø (In) FOUND-ATION	lb/ft 3.0	3.5	4.0	5.0	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
SNTH 139 RICHFORD (CONT.)																																				
15+74, LT		1	30	30	6.25						5.75																						RI-1		X		
		1	18	6	0.75						1						X	X	1														RI-3P	SLEEVE TO BE INSTALLED IN EXISTING SIDEWALK PER VAOT STANDARD T-45	X		
		1	24	24	4.00																												R3-1		X		
15+74, LT	B-B	1	30	30	6.25						4.25																						R5-1	SLEEVE TO BE INSTALLED IN EXISTING SIDEWALK PER VAOT STANDARD T-45	X		
		1	36	12	3.00						1					X		X	1														R6-1	INSTALL 90 DEGREES TO SIGN R5-1	X		
		1	36	12	3.00																												R6-1	INSTALL 90 DEGREES TO SIGN R5-1	X		
16+16, RT		1	12	18	1.50						2.25					X		X	1														R7-8	SLEEVE TO BE INSTALLED IN EXISTING SIDEWALK PER VAOT STANDARD T-45	X		
16+30, LT		1	12	18	1.50						0.50					X		X	1														R7-5	SLEEVE TO BE INSTALLED IN EXISTING SIDEWALK PER VAOT STANDARD T-45	X		
16+61, RT		1	12	18	1.50						0.25					X		X	1														R7-5	SLEEVE TO BE INSTALLED IN EXISTING SIDEWALK PER VAOT STANDARD T-45	X		
17+17, LT		1	12	18	1.50						0.25					X		X	1														R7-5	SLEEVE TO BE INSTALLED IN EXISTING SIDEWALK PER VAOT STANDARD T-45	X		
												FT	FT	FT	FT	FT 64	FT 15		EA 6	LB	LB	LB		LB	LB	LB	LB									
TOTALS					SF 29.25	SF	EA.	SF				FT			FT 79					LB			EA.	LB				EA.	EA.	LB					

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #25

PROJECT NAME: ENOSBURG-RICHFORD
PROJECT NUMBER: STP 2939(1)

FILE NAME: p11b312.dgn
PROJECT LEADER: J. LITTLE
DESIGNED BY: J. LITTLE
IPARM FILE: p11b312tss25.i

PLOT DATE: 3/19/2014
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 97 OF 115