

STATE OF VERMONT AGENCY OF TRANSPORTATION												QUANTITY SHEET 2											
SUMMARY OF ESTIMATED QUANTITIES												TOTALS		DESCRIPTIONS						DETAILED SUMMARY OF QUANTITIES			
						ROADWAY	CULVERT	EROSION CONTROL	TRAINING	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS			
						1						1		EACH	PRECAST REINFORCED CONCRETE DROP INLET WITH CAST IRON GRATE	604.18							
						1						1		EACH	CHANGING ELEVATION OF DROP INLETS, CATCH BASINS, OR MANHOLES	604.40							
								10				10		HR	ALL PURPOSE EXCAVATOR RENTAL, TYPE I	608.25							
								1				1		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15							
						45						45		CY	STONE FILL, TYPE II	613.11							
							1100					1100		CY	STONE FILL, TYPE III	613.12							
										2550		2550		CY	STONE FILL, TYPE IV	613.13							
						195						195		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28							
						120						120		SY	PORTLAND CEMENT CONCRETE SIDEWALK, 5 INCH	618.10							
						8						8		SF	DETECTABLE WARNING SURFACE	618.30							
						5						5		EACH	STEEL MARKER POSTS	619.16							
						292						292		LF	BOX BEAM GUARDRAIL	621.30							
						1						1		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51							
						98						98		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80							
						200						200		HR	UNIFORMED TRAFFIC OFFICERS	630.10							
						600						600		HR	FLAGGERS	630.15							
											1	1		LS	FIELD OFFICE, ENGINEERS	631.10							
											1	1		LS	TESTING EQUIPMENT, CONCRETE	631.16							
											1	1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17							
											5000	5000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26							
									520			520		HR	EMPLOYEE TRAINEESHIP	634.10							
						1						1		LS	MOBILIZATION/DEMOBILIZATION	635.11							
						1150						1150		LF	4 INCH WHITE LINE	646.20							
						1190						1190		LF	4 INCH YELLOW LINE	646.21							
						12						12		LF	24 INCH STOP BAR	646.26							
						4						4		EACH	LETTER OR SYMBOL	646.30							
							1000			2400		3400		SY	GEOTEXTILE UNDER STONE FILL	649.31							
								150				150		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515							
								400				400		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61							
								40				40		LB	SEED	651.15							
								240				240		LB	FERTILIZER	651.18							
								1				1		TON	AGRICULTURAL LIMESTONE	651.20							
								1				1		TON	HAY MULCH	651.25							
								250				250		CY	TOPSOIL	651.35							
								1800				1800		SY	GRUBBING MATERIAL	651.40							
								1				1		LS	EPSC PLAN	652.10							
								100				100		HR	MONITORING EPSC PLAN	652.20							
								1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30							
								290				290		SY	TEMPORARY EROSION MATTING	653.20							
								90				90		CY	VEHICLE TRACKING PAD	653.35							
																		PROJECT NAME: JAMAICA					
																		PROJECT NUMBER: ER-BRF 015-1(23)					
																		FILE NAME: s1lb316quantitysheet.dgn					
																		PLOT DATE: 03-JAN-2013					
																		PROJECT LEADER: K. HIGGINS					
																		DRAWN BY: G. LAROCHE					
																		DESIGNED BY: G. LAROCHE					
																		CHECKED BY: K. FRIEDLAND					
																		QUANTITY SHEET 2					
																		SHEET 6 OF 82					