

QUANTITY SHEET 2 BENNINGTON

SUMMARY OF ESTIMATED QUANTITIES					TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
	ROADWAY	EROSION CONTROL	BRIDGE	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
	1				1		LS	TRAFFIC CONTROL	641.10				
	2				2		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15				
		1080			1080		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	6.3			
			240		240		SY	GEOTEXTILE UNDER STONE FILL	649.31				
		150			150		SY	GEOTEXTILE FOR SILT FENCE	649.51	7.3			
		30			30		LB	SEED	651.15	EST.			
		250			250		LB	FERTILIZER	651.18	EST.			
		1			1		TON	AGRICULTURAL LIMESTONE	651.20	EST.			
		1			1		TON	HAY MULCH	651.25	EST.			
		40			40		CY	TOPSOIL	651.35	EST.			
		1			1		LS	EPSC PLAN	652.10				
		40			40		HR	MONITORING EPSC PLAN	652.20				
		1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
		100			100		SY	TEMPORARY EROSION MATTING	653.20	EST.			
		50			50		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25	2.0			
		55			55		CY	VEHICLE TRACKING PAD	653.35	6.4			
		1300			1300		LF	PROJECT DEMARCATION FENCE	653.55	13.0			
			74		74		EACH	SPECIAL PROVISION (MICROPILE)	900.620				
			2		2		EACH	SPECIAL PROVISION (MICROPILE VERIFICATION LOAD TEST)	900.620				
			350		350		LF	SPECIAL PROVISION (CORING CONCRETE)	900.640				
			1		1		LS	SPECIAL PROVISION (FURNISHING EQUIPMENT FOR INSTALLING MICROPILES)	900.645				

FILE NAME: V:\Projects\BENNINGTON\BENNINGTON\MSTN\z11b326-quant_02.dgn
DATE/TIME: 8/21/2012
USER: 4986



QUANTITY SHEET #2

PROJECT NAME: BENNINGTON	PLOT DATE: 8/21/2012
PROJECT NUMBER: ER BHF 010-1(45)	DRAWN BY: M.E.D.
FILE NAME: z11b326-quant_02.dgn	CHECKED BY: D.E.G.
DESIGNED BY: K.J.K.	SHEET 5 OF 40
DWG. NO.: z11b326quant02.1	