STATE OF VERMONT
AGENCY OF TRANSPORTATION

ITEM DETAIL SHEET 1

BEGIN STATION	END STATION	POS.	203.30 EARTH BORROW	604.412, 604.415, 604.418 REHAB. DI, CB OR MH CLASS I, II, III	613.10 STONE FILL, TYPE I	616.41 REMOVAL OF EXIST. CURB	619.17 YIELD MARKER POSTS	621.20 STEEL BEAM G.R. GALV.	621.50 MTS FLARED	621.51 MTS TANGENT	621.76 REPLACE G.R. POST ASSEMBLY	621.77 REPLACE G.R. BEAM UNIT	621.80 REMOVE & DISP. OF G.R.	649.51 GEOT. FOR SILT FENCE	651.35 TOPSOIL	653.20 TEMP. EROSION MATTING	676.10 DELINE. WITH STEEL POSTS	676.12 REMOVAL OF EXIST. DELINE.	900.680 AGG. SHOULD., RAS	REMARKS
			CY	EACH	CY	LF	EACH	LF	EA	EA	EACH	EACH	LF	SY	CY	SY	EACH	EACH	TON	
BERLIN				1	25		26								70				170	FOR USE AS DIRECTED BY ENGINEER
RAMP D			25					187.5	1				32		5	25	1	1		REMOVE BULL NOSE, EXTEND RAIL 187.5' & INSTALL MTS
RAMP C			25					150	1				32		5	25	1	1		REMOVE BULL NOSE, EXTEND RAIL 150' & INSTALL MTS
MM 0.024	MM 0.069	LT	25					187.5	1				32		5	25	1	1		REMOVE BULL NOSE, EXTEND RAIL 187.5' & INSTALL MTS
MM 0.024	MM 0.060	RT	25					150	1				32		5	25	1	1		REMOVE BULL NOSE, EXTEND RAIL 150' & INSTALL MTS
MM 0.089	MM 0.132	LT	25					187.5	1				32		5	25	1	1		REMOVE BULL NOSE, EXTEND RAIL 187.5' & INSTALL MTS
MM 0.097	MM 0.132	RT	25					150	1				32		5	25	1	1		REMOVE BULL NOSE, EXTEND RAIL 150' & INSTALL MTS
MM 0.136	MM 0.153	LT	25					50		1			32		5	25	1	1		REMOVE BULL NOSE, EXTEND RAIL 50' & INSTALL MTS
MM 0.136	MM 0.149	RT	25					12.5		1			32		5	25	1	1		REMOVE BULL NOSE, EXTEND RAIL 12.5' & INSTALL MTS
MM 0.125	MM 0.201	LT	25						1		1	14	38		5	25	1	1		
MM 0.293	MM 0.348	RT	50						2			1	75		10	50	2	2		
MM 0.711		LT			2															REPAIR EROSION AROUND HEADWALL
MM 0.716	MM 0.934	LT	50						2		6	24	75		10	50	2	2		
MM 0.874	MM 0.942	RT	50						2		1	4	75		10	50	2	2		
MM 0.884	MM 0.933	RT			95	259								115						REMOVE CURBING & INSTALL STONE FILL, TYPE I
SUBTOTAL			375	1	122	259	26	1075	13	2	8	43	519	115	145	375	15	15	170	

PROJECT NAME: BERLIN-BARRE TOWN
PROJECT NUMBER: STP 2943(I)

FILE NAME: z11b3381ds.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: S. SOLLA
ITEM DETAIL SHEET 1

PLOT DATE: 4/26/2016
DRAWN BY: O. DALMER
CHECKED BY: C. LATHROP
SHEET 26 OF 202