STATE OF VERMONT
AGENCY OF TRANSPORTATION

# TRAFFIC SIGN SUMMARY SHEET 3

| MILE MARKER, STATION OR SIGN NUMBER | | SIGN DIMENSIONS | | | NEW & SALVAGED SIGNS | | | | EXIST POST | | NEW SIGN POSTS | | | | | | | | | | | | | | | | | | | | | | REMARKS | SIGN DETAIL | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | EACH | WIDTH (in) | HEIGHT (in) | "A" | "B" | SALV SIGN | SALV TIS | RETAIN | SALVAGE | NO. OF POST | FLANGED CHANNEL (LB / FT) | | | SQUARE STEEL (in) (LB / FT) | | | ANCHOR | SLEEVE | TUBULAR ALUMINUM Ø (IN) (LB / FT) | | | FOUND-ATION | TUBULAR STEEL Ø (IN) (LB / FT) | | | | W-SHAPE STEEL FTG. SIZE | | WEIGHT | POST SIZE | SIGN FRAME REQUIRED | SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK | DETAIL IN SHSM | DETAIL ON SHEET NUMBER | STANDARD SHEET NUMBER |
| | | | | | | | | | | | | 1.12 | 2.00 | 3.00 | 1.75 | 2.00 | 2.50 | | | 3.00 | 4.00 | 4.0 MOD | | 3.00 | 3.50 | 4.00 | 5.00 | 24" | 30" | | | | | | |
| | | | | | | | | | | | | | | | 1.88 | 2.42 | 3.35 | | | 1.30 | 1.70 | 1.70 | | 7.60 | 9.00 | 10.80 | 14.60 | | | | | | | | |
| OPTION ITEMS | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| MM 0.371 RT BERLIN | *WORK ORDER NOT TO MOVE* 4 GAS/DIESEL | 1 | 72 | 10 | 5.00 | | | | | | 2 | | | | | ~~30~~ | | ~~X~~ | | | | | | | | | | | | | | VD-502 | | 64 | |
| | *WORK ORDER NOT TO MOVE* 4 FOOD | 1 | 72 | 10 | 5.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | VD-502 | | 64 | |
| | *WORK ORDER NOT TO MOVE* 5 LODGING | 1 | 72 | 10 | 5.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | VD-502 | | 64 | |
| | *WORK ORDER NOT TO MOVE* 5 CAMPING | 1 | 72 | 10 | 5.00 | | | | | | | | | | | | | | | | | | | | | | | | | | | VD-502 | | 64 | |
| MM 0.400 LT BERLIN | 0630 1203 0040 7-21-17 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | 8 | | | 7.75 X | | | | | | | | | | | | | | VD-700 | | | T-44 |
| MM 0.600 RT BERLIN | 0630 1203 0060 5-4-17 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | 8 | | | 9 X | | | | | | | | | | | | | | VD-700 | | | T-44 |
| MM 0.652 RT BERLIN | UNSAFE TO PASS 5-8-17 | 1 | 36 | 36 | 9.00 | | | | | | 2 | | | | | 30 | | 15 X 14 | | | | | | | | | | | | | | VW-092 | | | E-150 |
| MM 0.800 LT BERLIN | 0630 1203 0080 7-21-17 | 1 | 6 | 10 | 0.42 | | | | | | 1 | | | | 8 | | | 8 X | | | | | | | | | | | | | | VD-700 | | | T-44 |
| MM 0.938 LT BERLIN | SLOWER TRAFFIC KEEP RIGHT 5-4-17 | 1 | 36 | 48 | 12.00 | | | | 2 | | | | | | | | | | | | | | | | | | | | | | | R4-3 | SHSM | | |
| | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | | FT 24 | FT ~~60~~ 29 | FT 0 | | EA | | | | | LB | LB | LB | LB | | | | | | | | |
| TOTALS | | | | | SF 42.26 | SF | EA. 0 | SF | | | | FT | | | FT 84 | | | | | LB | | | EA. | LB | | | | EA. | EA. | LB | | | | | |

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: BERLIN-BARRE TOWN
PROJECT NUMBER: STP 2943(I)

FILE NAME: zllb338tsss.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: S. SOLLA
TRAFFIC SIGN SUMMARY SHEET 3

PLOT DATE: 4/26/2016
DRAWN BY: O. DALMER
CHECKED BY: C. LATHROP