STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 14

MILE MARKER, STATION OR SIGN NUMBER		SIGN DIMENSIONS EACH	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	SALVAGE	NEW SIGN POSTS NO. OF POST	FLANGED CHANNEL (LB / FT) 1.12	2.00	3.00	SQUARE STEEL (in) (LB / FT) 1.75 1.88	2.00 2.42	2.50 3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) (LB / FT) 3.00 1.30	4.00 1.70	4.0 MOD 1.70	FOUND-ATION	TUBULAR STEEL Ø (IN) (LB / FT) 3.00 7.60	3.50 9.00	4.00 10.80	5.00 14.60	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	SIGN DETAIL DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
OPTION ITEMS																																					
MM BT 2.742 C/L BARRE TOWN	5-25-17	1	24	18	3.00						1					15		15.75 X															R14-1 BLACK ON WHITE	SHSM		
		1	24	12	2.00																												M4-5 BLACK ON WHITE	SHSM		
		1	24	12	2.00																												VD-326 BLACK ON WHITE		63	
		1	21	15	2.19																												M5-1 BLACK ON WHITE	SHSM		
MM BT 2.777 RT BARRE TOWN	5-4-17	1 1	21 24	15 12			1 1				2					30		15 X 14.25														#1A	M2-1 GREEN ON WHITE SALVAGE SIGN ON NEW POST M4-6 GREEN ON WHITE SALVAGE SIGN ON NEW POST			
		1 1	24 24	24 24			1 1																										M1-5 SALVAGE SIGN ON NEW POST M1-5 SALVAGE SIGN ON NEW POST			
MM BT 2.800 LT BARRE TOWN	5-2-17	1	6	10	0.42						1				8			7 X															VD-700			T-44
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."															FT ~~8~~ 7	FT 45	FT 0		EA					LB	LB	LB	LB									
		TOTALS			SF 9.61	SF	EA. 4	SF				FT			FT ~~53~~ 52					LB			EA.	LB				EA.	EA.	LB						

PROJECT NAME: BERLIN-BARRE TOWN
PROJECT NUMBER: STP 2943(I)

FILE NAME: z11b338tsss.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: S. SOLLA
TRAFFIC SIGN SUMMARY SHEET 14

PLOT DATE: 4/26/2016
DRAWN BY: O. DALMER
CHECKED BY: C. LATHROP
SHEET 59 OF 202