STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 7

MILE MARKER, STATION OR SIGN NUMBER		SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																						REMARKS	SIGN DETAIL		
											NO. OF	FLANGED CHANNEL (LB / FT)			SQUARE STEEL (in) (LB / FT)					TUBULAR ALUMINUM Ø (IN) (LB / FT)				TUBULAR STEEL Ø (IN) (LB / FT)					W-SHAPE STEEL							
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	POST	1.12	2.00	3.00	1.75 1.88	2.00 2.42	2.50 3.35	ANCHOR	SLEEVE	3.00 1.30	4.00 1.70	4.0 MOD 1.70	FOUND-ATION	3.00 7.60	3.50 9.00	4.00 10.80	5.00 14.60	FTG. SIZE 24"	FTG. SIZE 30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
OPTION ITEMS																																		
MM 1.122 RT NORTHFIELD	Glacier Valley Rd Pvt 5-3-17	1	72	12	6.00						2					30		12 X 12														D3-1		136	
MM 1.200 LT NORTHFIELD	0640 1213 0120 4-27-17	1	6	10	0.42						1				8			7 X														VD-700			T-44
MM 1.256 LT NORTHFIELD	RUNAWAY TRUCK RAMP 1 MILE 7-28-17	1	78	48		26.00			2																						W7-4 --- MOUNT SIGN ON RETAINED TUBULAR STEEL POSTS	SHSM		
MM 1.326 LT NORTHFIELD	STOP 4-27-17	1	30	30	6.25						1					15		13.25 X														R1-1 BACK TO BACK	SHSM		
	0640 1213 0133	1	6	10	0.42																											VD-700 BACK TO BACK			T-44
MM 1.334 LT NORTHFIELD	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00				1																							VR-017 --- MOUNT SIGN ON RETAINED FLANGED CHANNEL POST			T-70
MM 1.334 LT NORTHFIELD	Barrows Rd	1	54	12	4.50						2					30		11.25 X 11.75														D3-1		136	
MM 1.349 RT NORTHFIELD	BRIDGE 1A VT 64 4-28-17	1	6	10	0.42						1				8			8 X														VD-701			T-42
MM 1.387 LT NORTHFIELD	BRIDGE 1A VT 64	1	6	10	0.42						1				8			7.5 X														VD-701			T-42
															FT 24	FT 75	FT		EA				LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."	TOTALS		SF 23.43	SF 26.	EA.	SF			FT		FT 99								LB		EA.		LB				EA.	EA.	LB						

PROJECT NAME: NORTHFIELD-WILLIAMSTOWN
PROJECT NUMBER: STP 2959(I)

FILE NAME: zl5v022tsss.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: J. GOODALL
TRAFFIC SIGN SUMMARY SHEET 7

PLOT DATE: 4/26/2016
DRAWN BY: O. DALMER
CHECKED BY: C. LATHROP
SHEET III OF 202