STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 11

MILE MARKER, STATION OR SIGN NUMBER		SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																						REMARKS	SIGN DETAIL		
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POST	FLANGED CHANNEL (LB / FT)			SQUARE STEEL (in) (LB / FT)			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) (LB / FT)			FOUND-ATION	TUBULAR STEEL Ø (IN) (LB / FT)				W-SHAPE STEEL FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME REQUIRED		DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
															1.75	2.00	2.50			3.00	4.00	4.0 MOD		3.00	3.50	4.00	5.00						SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK			
												1.12	2.00	3.00	1.88	2.42	3.35			1.30	1.70	1.70		7.60	9.00	10.80	14.60	24"	30"						
OPTION ITEMS																																				
RT MM 2.198 ~~LT~~ NORTHFIELD	STOP 4-26-17	1	30	30	6.25						1					15		13.5 x															R1-1 BACK TO BACK	SHSM		
	0640 1213 0220 4-27-17	1	6	10	0.42																												VD-700 BACK TO BACK			T-44
MM 2.199 RT NORTHFIELD	Robinson Rd 4-26-17	1	60	12	5.00						2					30		11.5 X 11.25															D3-1		136	
MM 2.201 RT NORTHFIELD	BRIDGE 2A VT 64	1	6	10	0.42						1				8			7.5 X															VD-701			T-42
MM 2.400 LT NORTHFIELD	0640 1213 0240	1	6	10	0.42						1				8			8.5 X															VD-700			T-44
MM 2.418 RT NORTHFIELD	BRIDGE 2B VT 64 4-27-17	1	6	10	0.42						1				8			8.75 X															VD-701			T-42
												FT 24	FT	FT	FT 45	FT	FT	EA						LB	LB	LB	LB									
	TOTALS				SF 12.93	SF	EA.	SF				FT			FT 69				LB			EA.		LB				EA.	EA.	LB						

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: NORTHFIELD-WILLIAMSTOWN
PROJECT NUMBER: STP 2959(I)

FILE NAME: zl5v022tsss.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: J. GOODALL
TRAFFIC SIGN SUMMARY SHEET II

PLOT DATE: 4/26/2016
DRAWN BY: O. DALMER
CHECKED BY: C. LATHROP
SHEET 115 OF 202