STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 26

MILE MARKER, STATION OR SIGN NUMBER		SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																					REMARKS	SIGN DETAIL		
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POST	FLANGED CHANNEL (LB / FT)			SQUARE STEEL (in) (LB / FT)			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) (LB / FT)			FOUND-ATION	TUBULAR STEEL Ø (IN) (LB / FT)				W-SHAPE STEEL					SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
															1.75	2.00	2.50			3.00	4.00	4.0 MOD		3.00	3.50	4.00	5.00	FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME REQUIRED			
												1.12	2.00	3.00	1.88	2.42	3.35			1.30	1.70	1.70		7.60	9.00	10.80	14.60	24"	30"						
OPTION ITEMS																																			
MM W 3.112 LT WILLIAMSTOWN	5-17-17	1	30	30																												W11-7 --- REMOVE EXISTING SIGN AT MM W 3.112 LT AND DO NOT REPLACE	SHSM		
MM W 3.112 LT WILLIAMSTOWN		1	30	30	6.25						1					15		15.5 X														W1-1R(MOD.) ---REMOVE EXISTING SIGN AT MM W 3.155 LT AND REPLACE 227 FEET WEST OF EXISTING LOCATION AT MM W 3.112 LT		136	
		1	18	18	2.25																											W13-1P ---REMOVE EXISTING SIGN AT MM W 3.155 LT AND REPLACE 227 FEET WEST OF EXISTING LOCATION AT MM W 3.112 LT	SHSM		
MM W 3.200 LT WILLIAMSTOWN		1	6	10	0.42						1				8			8.75 X														VD-700			T-44
MM W ~~3.230~~ 3.250 RT WILLIAMSTOWN		1	30	30	6.25						1					15		15 X														W1-1R --- REMOVE EXISTING SIGN AT MM W 3.230 RT AND REPLACE IN EXISTING LOCATION	SHSM		
		1	18	18	2.25																											W13-1P --- REMOVE EXISTING SIGN AT MM W 3.230 RT AND REPLACE IN EXISTING LOCATION	SHSM		
MM W 3.279 LT WILLIAMSTOWN		1	6	10	0.42						1				8			8.25 X														VD-701 --- REMOVE EXISTING SIGN AT MM W 3.279 LT AND REPLACE IN EXISTING LOCATION			T-42
MM W 3.284 RT WILLIAMSTOWN		1	6	10	0.42						1				8			7.5 X														VD-701 --- REMOVE EXISTING SIGN AT MM W 3.284 RT AND REPLACE IN EXISTING LOCATION			T-42
MM W 3.300 LT WILLIAMSTOWN	5-16-17	1	54	12	4.50						2					30		10 X 10														D3-1 --- REMOVE EXISTING SIGN AT MM W 3.300 LT AND REPLACE IN EXISTING LOCATION		136	
MM W 3.330 RT WILLIAMSTOWN	5-17-17	1	36	36	9.00						2					30		14 X 14.25														S3-1 --- REMOVE EXISTING SIGN AT MM W 3.330 RT AND REPLACE IN EXISTING LOCATION. SIGN WILL BE FLUORESCENT YELLOW-GREEN, WITH TYPE IX SHEETING	SHSM		
												FT 24			FT 90		FT		EA				LB	LB	LB	LB								
FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."																																			
	TOTALS				SF 31.76	SF	EA.	SF				FT			FT 114					LB			EA.	LB				EA.	EA.	LB					

PROJECT NAME: NORTHFIELD-WILLIAMSTOWN
PROJECT NUMBER: STP 2959(I)

FILE NAME: zl5v022tsss.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: J. GOODALL
TRAFFIC SIGN SUMMARY SHEET 26

PLOT DATE: 4/26/2016
DRAWN BY: O. DALMER
CHECKED BY: C. LATHROP
SHEET 130 OF 202