STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 29

MILE MARKER, STATION OR SIGN NUMBER		SIGN DIMENSIONS			NEW & SALVAGED SIGNS				EXIST POST		NEW SIGN POSTS																				REMARKS	SIGN DETAIL		
		EACH	WIDTH (in)	HEIGHT (in)	"A"	"B"	SALV SIGN	SALV TIS	RETAIN	SALVAGE	NO. OF POST	FLANGED CHANNEL (LB / FT)			SQUARE STEEL (in) (LB / FT)			ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (IN) (LB / FT)			FOUND-ATION	TUBULAR STEEL Ø (IN) (LB / FT)				W-SHAPE STEEL					SHSM = FHWA STANDARD HIGHWAY SIGNS AND MARKINGS BOOK	DETAIL IN SHSM	DETAIL ON SHEET NUMBER	STANDARD SHEET NUMBER
															1.75	2.00	2.50			3.00	4.00	4.0 MOD		3.00	3.50	4.00	5.00	FTG. SIZE		WEIGHT	POST SIZE	SIGN FRAME REQUIRED				
												1.12	2.00	3.00	1.88	2.42	3.35			1.30	1.70	1.70		7.60	9.00	10.80	14.60	24"	30"						
OPTION ITEMS																																			
MM W 3.893 LT WILLIAMSTOWN	5-23-17	1	30	30	6.25						1					15		X 14.25															W11-6 --- REMOVE EXISTING SIGN AT MM W 3.950 LT AND REPLACE 300 FEET WEST OF EXISTING LOCATION AT MM W 3.893 LT. HINGED SIGN, INSTALL IN CLOSED POSITION	SHSM		
MM W 3.977 RT WILLIAMSTOWN	5-25-17 Williamstown Schools	1	72	20	10.00						2					30		14 X 13															VD2-1 --- REMOVE EXISTING SIGN AT MM W 3.977 RT AND REPLACE IN EXISTING POSITION			T-93
MM W 4.000 LT WILLIAMSTOWN	5-18-17 WEST	1	24	12	2.00		1 *EXISTING MM				1					15		14.25 X															M3-4 --- REMOVE EXISTING SIGN AT MM W 4.000 LT AND REPLACE IN EXISTING LOCATION	SHSM		
	VERMONT 64	1	~~30~~ 24	24	~~5.00~~ 4																												M1-5 --- REMOVE EXISTING SIGN AT MM W 4.000 LT AND REPLACE IN EXISTING LOCATION			E-136B
MM W 4.033 LT WILLIAMSTOWN	Brush Hill Rd	1	66	12	5.50						2					30		10.25 X 10.25															D3-1 --- REMOVE EXISTING SIGN AT MM W 4.033 LT AND REPLACE IN EXISTING LOCATION		136	
MM W 4.033 LT WILLIAMSTOWN	STOP	1	30	30	6.25						1					15		13.5 X															R1-1 --- REMOVE EXISTING SIGN AT MM W 4.033 LT AND REPLACE IN EXISTING LOCATION	SHSM		
	0140 0917 0401	1	6	10	0.42																												VD-700 --- REMOVE EXISTING SIGN AT MM W 4.033 LT AND REPLACE IN EXISTING LOCATION. MOUNT MILE MARKER BACK TO BACK WITH STOP SIGN			T-44
MM W 4.038 LT WILLIAMSTOWN	LEGAL LOAD LIMIT 24,000 POUNDS	1	24	30	5.00						1					15		13.25 X															VR-017 --- REMOVE EXISTING SIGN AT MM W 4.038 LT AND REPLACE IN EXISTING LOCATION			T-70
												FT			FT	FT 120	FT		EA					LB	LB	LB	LB								
TOTALS					SF 40.42	SF	EA.	SF				FT			FT 120					LB			EA.	LB				EA.	EA.	LB					

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

PROJECT NAME: NORTHFIELD-WILLIAMSTOWN
PROJECT NUMBER: STP 2959(I)

FILE NAME: zl5v022tsss.dgn
PROJECT LEADER: C. LATHROP
DESIGNED BY: J. GOODALL
TRAFFIC SIGN SUMMARY SHEET 29

PLOT DATE: 4/26/2016
DRAWN BY: O. DALMER
CHECKED BY: C. LATHROP
SHEET 133 OF 202