

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
							ROADWAY	BRIDGE	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
									1000	1000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			TEMPORARY EROSION MATTING
							0.33			0.33		LS	MOBILIZATION/DEMobilIZATION	635.11	-	1995	SY	DITCH CLEANING DETAIL SHEET
							1			1		LS	TRAFFIC CONTROL (STP 2960(1))	641.10	-	500	SY	ITEM DETAIL SHEET
							4			4		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-	153	SY	EPSC SHEET
													BEGIN OPTION BB			52	SY	ROUNDING
							22750			22750		LF	DURABLE 4 INCH WHITE LINE, THERMOPLASTIC	646.402	274	2700	SY	TOTAL
							22750			22750		LF	DURABLE 4 INCH WHITE LINE, EPOXY PAINT	646.403	274			
							22750			22750		LF	DURABLE 4 INCH WHITE LINE, POLYUREA	646.404	274			
													END OPTION BB					
													BEGIN OPTION DD					
							23250			23250		LF	DURABLE 4 INCH YELLOW LINE, THERMOPLASTIC	646.412				
							23250			23250		LF	DURABLE 4 INCH YELLOW LINE, EPOXY PAINT	646.413				
							23250			23250		LF	DURABLE 4 INCH YELLOW LINE, POLYUREA	646.414				
													END OPTION DD					
													BEGIN OPTION JJ					
							70			70		LF	DURABLE 24 INCH STOP BAR, THERMOPLASTIC	646.482				
							70			70		LF	DURABLE 24 INCH STOP BAR, EPOXY PAINT	646.483				
							70			70		LF	DURABLE 24 INCH STOP BAR, POLYUREA	646.484				
													END OPTION JJ					
													BEGIN OPTION KK					
							25			25		EACH	DURABLE LETTER OR SYMBOL, THERMOPLASTIC	646.492				
							25			25		EACH	DURABLE LETTER OR SYMBOL, EPOXY PAINT	646.493				
							25			25		EACH	DURABLE LETTER OR SYMBOL, POLYUREA	646.494				
													END OPTION KK					
							23000			23000		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	300			
							23500			23500		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	429			
							110			110		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	10			
							25			25		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
							4700			4700		EACH	LINE STRIPING TARGETS	646.76	38			
							475			475		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11	5			
							1625			1625		SY	GEOTEXTILE FOR SILT FENCE	649.51	35			
							160			160		LB	SEED	651.15	EST.			
							320			320		LB	FERTILIZER	651.18	EST.			
							2			2		TON	AGRICULTURAL LIMESTONE	651.20	0.7			
							2			2		TON	HAY MULCH	651.25	0.7			
							230			230		CY	TOPSOIL	651.35	5			
							1			1		LS	EPSC PLAN	652.10				
							50			50		HR	MONITORING EPSC PLAN	652.20	EST.			
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
							2700			2700		SY	TEMPORARY EROSION MATTING	653.20	52			

PROJECT NAME: BROOKFIELD
 PROJECT NUMBER: STP 2960(I)
 FILE NAME: z15v023quant.dgn
 PROJECT LEADER: C. LATHROP
 DESIGNED BY: S. SOLLA
 QUANTITY SHEET 2
 PLOT DATE: 4/26/2016
 DRAWN BY: O. DALMER
 CHECKED BY: C. LATHROP
 SHEET 157 OF 202