

QUANTITY SHEET 3

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
							ROADWAY	BRIDGE	FULL C.E.	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1350			1350		LF	PROJECT DEMARCATION FENCE	653.55	38			SPECIAL PROVISION (AGGREGATE SURFACE, RAS)
							1			1		LS	TREE PROTECTION	656.85	-	4748	TON	MAINLINE
							430			430		SF	TRAFFIC SIGNS, TYPE A	675.20	10.18	920	TON	INTERSECTION IMPROVEMENT
							1160			1160		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341	8	108	TON	SIDEROAD APRONS
							110			110		EACH	REMOVING SIGNS (TYPE A)	675.50	-	36	TON	DRIVES
							7			7		EACH	ERECTING SALVAGED SIGNS	675.60	-	88	TON	ROUNDING
							20			20		EACH	DELINEATOR WITH STEEL POST	676.10	-	5900	TON	TOTAL
							20			20		EACH	REMOVAL OF EXISTING DELINEATOR	676.12	-			
							1			1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50	-			
							11			11		EACH	SPECIAL PROVISION (DECOMMISSION CURB DROP INLET)	900.620				
							8334			8334		LF	SPECIAL PROVISION (BOX BEAM GUARDRAIL W/7 FEET POSTS)	900.640	-			
							365			365		SY	SPECIAL PROVISION (HAND PLACED BITUMINOUS CONCRETE MATERIAL, DRIVES)	900.675	9			
							440			440		TON	SPECIAL PROVISION (AGGREGATE SHOULDERS, RAS)	900.680	14			
							5900			5900		TON	SPECIAL PROVISION (AGGREGATE SURFACE COURSE, RAS)	900.680	88			
							40			40		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT SURFACE PREPERATION, TYPE I)	900.680	EST.			
							5100			5100		TON	SPECIAL PROVISION (MATERIAL TRANSFER VEHICLE)	900.680	153			

PROJECT NAME: BROOKFIELD
 PROJECT NUMBER: STP 2960(I)
 FILE NAME: z15v023quant.dgn
 PROJECT LEADER: C. LATHROP
 DESIGNED BY: S. SOLLA
 QUANTITY SHEET 3
 PLOT DATE: 4/26/2016
 DRAWN BY: O. DALMER
 CHECKED BY: C. LATHROP
 SHEET 158 OF 202