



**Highway Tech** Signal Equipment Sales, Inc.  
8 Gardiner Road / P.O. Box 1200  
Sabbatus, ME 04280  
Tel. (207) 375-8248  
Fax (207) 375-8279

## Features

- Meets NEMA standards
- Base mounted
- Constructed of 0.125" thick aluminum
- "C" mounting channels on side and back walls for mounting shelves and panels
- 3-point latching mechanism of zinc plated steel
- Stainless steel door handle designed for padlock
- Stainless steel door hinge
- Optional Lifting Ears

## SPECIFICATIONS:

Outside dimensions:	55" H x 44" W x 26" deep
Opening Dimensions:	53" H x 41" W
Mounting Pattern	40.50" W x 18.50" D
Material:	Aluminum (.125" thick)
Finish:	Bare or Painted
Mounting:	Base Mounted
Locking System:	3-point locking system with Corbin #2 lock
Door Stops:	Three position bar stop at bottom of door
Ventilation:	Pleated fiber filter in door, fan with thermostatic control
Light:	Incandescent or optional flourescent, door switch activated

**APPROVED**

*By Taylor Sisson at 1:38 pm, Apr 01, 2015*

**Technology That Moves America**

Naztec, Inc. • 820 Park Two Drive • Sugar Land, Texas 77478 • Phone (281) 240-7233 • Fax (281) 240-7238

Email: [naztec@naztec.com](mailto:naztec@naztec.com) • <http://www.naztec.com>