


APPROVED




By Taylor Sisson at 1:40 pm, Apr 01, 2015




MODEL#	VZ-097RTC
Screen Size	9.7"
Max. Resolution	1024 x 768 @60Hz
Pixel Pitch	0.192mm x 0.192mm
Brightness	300cd/m² (Typical)
Contrast Ratio	600:1
Aspect Ratio	4:3
Viewing Angle (H/V)	178°/178°
Display Color	0.26 Million
Response Time	<35ms
Video System	NTSC/PAL
Frequency (H)	31~48Khz
Frequency (V)	56~60Hz
BACK PANEL	
AV(Composite)1 In/ Out(BNC Type)	1/1
AV(Composite)2 In/ Out(RCA Type)	1/1
RGB In(15 Pin D-Sub)	1
Trigger In	1
PC Stereo In	1
SPEAKER	
Built in speaker	1W x2
FEATURES	
Filter Type	2D Comb Filter/Deinterlace
LCD Protection Glass	Not Available
Video Resolution(Max)	520 TV Line
Multi-lingual Language	English, Spanish, French, German, Italian, Portuguese, Dutch
PHYSICAL	
Outline Dimension (W x H x D)	9.25" x 8.31" x 1.71"
Net Weight	(235mm x 211mm x 43.4mm) 2.73 lbs (1.24 kg)
INSTALL	
VESA	75mm x 75mm, M4x10 Screws
OTHER	
Transmitter / IR Remote Control	Not Available
Power - Electrical Ratings - Consumption	DC 12V, 0.68A(AC100 ~ 240V[50/60Hz]) 8.2W
Warranty: Parts/Labor	3 Year / 3 Year
MTBF (Approx)	30,000 Hours
Operating Temperature	32 - 104°F / 0 - 40°C
Regulations	CE, FCC, UL, FCC(A)
Compatible Mounts - WALL	VZ-WM05, VZ-WM10, VZ-WM31
- CEILING	VZ-CMK01, VZ-CMK02
- Rack	VZ-RMK08

VZ-097RTC ADVANTAGES:


- 9.7" LED CCTV Monitor
- 1024 x 768 Resolution
- BNC, RCA, VGA
- 2D Comb-filter, De-interlace, Built-in Speakers
- 3-Year Warranty



INTERFACE



1. TRIGGER IN
2. PC STEREO IN
3. AV(composite)1 IN/OUT (BNC Type)
4. AV(composite)2 IN/OUT (RCA Type)
5. VGA IN
6. DC 12V IN



Highway Tech

6 Sabattus Road - P.O. Box 1209 - Sabattus, ME 04280
 ME Office - Tel. (207) 375-8248 - Fax (866) 232-7014
 NY Office - Tel. (607) 299-4604 - Fax (866) 350-3162