



Terminal Compartment Assemblies

Designed to accommodate all traffic signals, with the exception of the optically programmed. The Astro-Brac features all-axis adjustability and is designed to facilitate the mounting of any size signal to any size of mast arm or pole.




Astro-Brac Assy, Mark I Terminal Compartment, 1-Way Band Mount

Signal Section	Band Length	Coating
AB-0140 - 3 & 4	42	P34
3=3 Sec	29=29" Band	PNC=Process No Color
4=4 Sec	36=36" Band	P__=Paint
5=5 Sec	42=42" Band	
	48=48" Band	
	56=56" Band	

For 3 & 4 Section Signals, Black Paint w Black Painted Bands


Note:
Stainless steel upgrade available; includes stainless clamp screw and slotted washer. Specify by including -SS in the part number, i.e., AB-0140-3-29-SS-PNC.



Astro-Brac Assy, Mark I Terminal Compartment, 1-Way Cable Mount

Signal Section	Cable Length	Coating
AB-0146 -		
3=3 Sec	62=62" Cable	PNC=Process No Color
4=4 Sec	84=84" Cable	P__=Paint
5=5 Sec	96=96" Cable	

Note:
Stainless steel upgrade available; includes stainless cable and slotted washer. Specify by including -SS in the part number, i.e., AB-0146-3-62-SS-PNC.



Astro-Brac Assy, Mark I Terminal Compartment, 5-Sec Cluster Cable Mount

Cable Length	Coating
AB-0147 -	
62=62" Cable	PNC=Process No Color
84=84" Cable	P__=Paint
96=96" Cable	

Note:
Stainless steel upgrade available; includes stainless cable and slotted washer. Specify by including -SS in the part number, i.e., AB-0147-62-SS-PNC.

- Note: 1. All assemblies are supplied standard with stainless steel fasteners.
2. See Reference Section for clamp kit pole diameters.
3. See Reference Section for available paint colors.

Astro-Brac

