

STATE OF VERMONT AGENCY OF TRANSPORTATION														QUANTITY SHEET 2									
SUMMARY OF ESTIMATED QUANTITIES												TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES					
								ROADWAY BR15	BRIDGE BR15	FULL C.E. ITEMS	ROADWAY BR22	BRIDGE BR22	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS		
								291			39		330		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80						
								100					100		HR	UNIFORMED TRAFFIC OFFICERS	630.10						
											320		320		HR	FLAGGERS	630.15						
										1			1		LS	FIELD OFFICE, ENGINEERS	631.10						
										1			1		LS	TESTING EQUIPMENT, CONCRETE	631.16						
										1			1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17						
										3000			3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26						
								1					1		LS	MOBILIZATION/DEMOBILIZATION	635.11						
								800			310		1110		LF	4 INCH WHITE LINE	646.20						
								800			310		1110		LF	4 INCH YELLOW LINE	646.21						
												570	570		SY	GEOTEXTILE UNDER STONE FILL	649.31						
												91	91		SY	GRUBBING MATERIAL	651.40						
								20					20		CY	VEHICLE TRACKING PAD	653.35						
								18					18		SF	TRAFFIC SIGNS, TYPE A	675.20						
								70					70		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341						
								7					7		EACH	REMOVING SIGNS	675.50						
								1					1		EACH	ERECTING SALVAGED SIGNS	675.60						
								1			1		2		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50						
								52	42				94		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOW CEMENT)	900.608						
												553	553		CY	SPECIAL PROVISION (STONE FILL, CHANNEL FLOW LINE)	900.608						
								4					4		EACH	SPECIAL PROVISION (GUARDRAIL APPROACH SECTION, GALVANIZED 3 RAIL BOX BEAM)	900.620						
									270				270		LF	SPECIAL PROVISION (BRIDGE RAILING, GALVANIZED 3 RAIL BOX BEAM)	900.640						
												1	1		LS	SPECIAL PROVISION (PEDESTAL WALL)(ABUTMENT NO.1)	900.645						
												1	1		LS	SPECIAL PROVISION (PEDESTAL WALL)(ABUTMENT NO.2)	900.645						
												1	1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM)	900.645						
											1		1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL INCLUSIVE)(ER 0187(9))	900.645						
								1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE)(BHF 0187(8))	900.645						
								1					1		LU	SPECIAL PROVISION (INCENTIVE)(N.A.B.I.)(BRIDGE 15)	900.650						
											1		1		LU	SPECIAL PROVISION (INCENTIVE)(N.A.B.I.)(BRIDGE 22)	900.650						
								1			1		2		LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC)(N.A.B.I.)	900.650						
								1			1		2		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650						
								1			1		2		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650						
									135				135		SY	SPECIAL PROVISION (PRECAST CONCRETE/STEEL COMPOSITE SUPERSTRUCTURE)	900.675						
								351	41		29		421		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680						