

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
			ROADWAY (BRIDGE 62A)	TRAINING	EROSION CONTROL (BRIDGE 62A)	BRIDGE (BRIDGE 62A)	FULL C.E. ITEMS	ROADWAY (BRIDGE 66)	BRIDGE (BRIDGE 66)	GRAND TOTAL	FNAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
			460							460		CY	COMMON EXCAVATION	203.15				
			1							1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22		460	CY	COMMON EXCAVATION (460 CY*1.00)
						200				200		CY	STRUCTURE EXCAVATION	204.25		150	CY	STRUCTURE EXCAVATION (200 CY*0.75)
						120				120		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30		610	CY	SUBTOTAL
			660							660		SY	COLD PLANNING, BITUMINOUS PAVEMENT	210.10		0	CY	ROUNDING
			420							420		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35		610	CY	TOTAL
			2							2		CWT	EMULSIFIED ASPHALT	404.65		610	CY	FILL AVAILABLE
			1							1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50		0	CY	FILL REQUIRED
						90				90		CY	CONCRETE, HIGH PERFORMANCE CLASS B	501.34		0	CY	BORROW
						6320				6320		LB	REINFORCING STEEL, LEVEL I	507.11		610	CY	WASTE
						25400				25400		LB	REINFORCING STEEL, LEVEL II	507.12				
						39				39		LF	DRILLING AND GROUTING DOVELS	507.16				
						1				1		LS	SHEAR CONNECTORS (880 - 7/8"x7")	508.15				
						15				15		GAL	WATER REPELLENT, SILANE	514.10				
						82				82		LF	BRIDGE EXPANSION JOINT, ASPHALTIC PLUG	518.10				
						279				279		LF	BRIDGE RAILING, GALVANIZED 2 RAIL BOX BEAM	525.33				
						318				318		SY	REMOVAL OF BRIDGE PAVEMENT	529.10				
						1				1		EACH	PARTIAL REMOVAL OF STRUCTURE (US5-BR. NO. 62A)	529.20				
									1	1		EACH	PARTIAL REMOVAL OF STRUCTURE (US5-BR. NO. 66)	529.20				
			6							6		LF	12" CPEP	601.0905				
			1							1		EACH	PRECAST REINFORCED CONCRETE CURB DI WITH CAST IRON GRATE	604.30				
			2880					720		3600		HR	TRUCK-MOUNTED ATTENUATOR	608.45				
					3					3		CY	STONE FILL, TYPE I	613.10	EST			
			200							200		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28				
			40							40		LF	REMOVING AND RESETTING FENCE	620.50				
						112				112		LF	SNOWBARRIER	620.75				
			125							125		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205				
			1							1		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50				
			1							1		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
			4							4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM	621.72				
			350							350		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						950			320	1270		LF	TEMPORARY TRAFFIC BARRIER	621.90				
						430				430		LF	REMOVE AND RESET TEMPORARY TRAFFIC BARRIER	621.95				
			150					150		300		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
			800					400		1200		HR	FLAGGERS	630.15				
							1			1		LS	FIELD OFFICE, ENGINEERS	631.10				
							1			1		LS	TESTING EQUIPMENT, CONCRETE	631.16				
							1			1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
							3000			3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
				520						520		HR	EMPLOYEE TRAINESHIP	634.10				

DELETE ITEM 621.60 FROM CONTRACT.

REV	DESCRIPTION	DATE
Δ	DELETED ITEM OR INCREASED QUANTITY	3-3-2014

PROJECT NAME: HARTLAND  
 PROJECT NUMBER: BHF BPNT (12)  
 FILE NAME: z11c260qs.dgn  
 PROJECT LEADER: W.A. COLGAN  
 DESIGNED BY: S.G. FARNSWORTH  
 QUANTITY SHEET 41  
 PLOT DATE: 02/28/2014  
 DRAWN BY: E.A. FIALA  
 CHECKED BY: S.G. FARNSWORTH  
 SHEET 7 OF 55

