

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
			ROADWAY (BRIDGE 62A)	TRAINING	EROSION CONTROL (BRIDGE 62A)	BRIDGE (BRIDGE 62A)	FULL C.E. ITEMS	ROADWAY (BRIDGE 66)	BRIDGE (BRIDGE 66)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
			0.5					0.5		1		LS	MOBILIZATION/DEMOBILIZATION	635.11				SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)
			1							1		LS	TRAFFIC CONTROL (US5-BR. NO. 62A)	641.10		197	TON	TYPE IIS
								1		1		LS	TRAFFIC CONTROL (US5-BR. NO. 66)	641.10		98	TON	TYPE IVS
			3					3		6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15		295	TON	SUBTOTAL
			650							650		LF	4 INCH WHITE LINE	646.20		5	TON	ROUND
			650							650		LF	4 INCH YELLOW LINE	646.21		300	TON	TOTAL
			800					500		1300		LF	TEMPORARY 4 INCH WHITE LINE, TYPE II TAPE	646.601				
			800					500		1300		LF	TEMPORARY 4 INCH YELLOW LINE, TYPE II TAPE	646.611				
			433							433		SF	PAVEMENT MARKING MASK	646.86				
					310					310		SY	GEOTEXTILE FOR SILT FENCE	649.51				
					10					10		LB	SEED	651.15				
					70					70		LB	FERTILIZER	651.18				
					0.3					0.3		TON	AGRICULTURAL LIMESTONE	651.20				
					0.3					0.3		TON	HAY MULCH	651.25				
					1					1		LS	EPSC PLAN	652.10				
					30					30		HR	MONITORING EPSC PLAN	652.20				
					1					1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.)	652.30				
					175					175		SY	TEMPORARY EROSION MATTING	653.20				
					15					15		CY	VEHICLE TRACKING PAD	653.35				
					460					460		LF	PROJECT DEMARCATION FENCE	653.55				
			1							1		SF	TRAFFIC SIGNS, TYPE A	675.20				
			14							14		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
						115				115		CY	SPECIAL PROVISION (HIGH PERFORMANCE CONCRETE, CLASS A LOWCEMENT) (FPQ)	900.608				
			1					1		2		EACH	SPECIAL PROVISION (TEMPORARY TRAFFIC SIGNAL SYSTEM, PORTABLE)	900.620				
									82	82		LF	SPECIAL PROVISION (REMOVE AND REPLACE DRAIN TROUGH)	900.640				
									82	82		LF	SPECIAL PROVISION (REMOVE AND RESTORE DRAIN TROUGH)	900.640				
									1	1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES) (US5-BR. NO. 66)	900.645				
						1				1		LS	SPECIAL PROVISION (CONTAINMENT AND DISPOSAL OF LEAD PAINT CLEANING RESIDUES) (US5-BR. NO. 62A)	900.645				
			1							1		LS	SPECIAL PROVISION (PUBLIC PROTECTION FOR BRIDGE PROJECTS)	900.645				
						1				1		LS	SPECIAL PROVISION (QC/QA CLEAN AND PAINT EXISTING STEEL STRUCTURES, BARE STEEL) (US5-BR. NO. 62A)	900.645				
									1	1		LS	SPECIAL PROVISION (QC/QA CLEAN AND PAINT EXISTING STEEL STRUCTURES, BARE STEEL) (US5-BR. NO. 66)	900.645				
						1				1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE) (N.A.B.I.)	900.650				
						1			1	2		LU	SPECIAL PROVISION (MAINTENANCE OF RAILROAD TRAFFIC) (N.A.B.I.)	900.650				
			1							1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY) (N.A.B.I.)	900.650				
			1							1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT) (N.A.B.I.)	900.650				
			215							215		SF	SPECIAL PROVISION (RETAINING WALL)	900.670				
			300							300		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: **HARTLAND**
 PROJECT NUMBER: **BHF BPNT (12)**
 FILE NAME: z11c260qs.dgn
 PROJECT LEADER: MA. COLGAN
 DESIGNED BY: S.G. FARNSWORTH
 QUANTITY SHEET #2

PLOT DATE: 01/03/2014
 DRAWN BY: E.A. FIALA
 CHECKED BY: S.G. FARNSWORTH
 SHEET 8 OF 55

