

# QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
					ROADWAY	EROSION CONTROL	BRIDGE NO. 6	BRIDGE NO. 7	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
					40					40		LB	SEED	651.15				
					270					270		LB	FERTILIZER	651.18				
					2					2		TON	AGRICULTURAL LIMESTONE	651.20				
					2					2		TON	HAY MULCH	651.25				
					180					180		CY	TOPSOIL	651.35				
					610					610		SY	GRUBBING MATERIAL	651.40				
						1				1		LS	EPSC PLAN (VT 58 - BRIDGE NO. 6)	652.10				
						1				1		LS	EPSC PLAN (VT 58 - BRIDGE NO. 7)	652.10				
						80				80		HR	MONITORING EPSC PLAN	652.20				
						1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (VT 58 - BRIDGE NO. 6)	652.30				
						1				1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (VT 58 - BRIDGE NO. 7)	652.30				
					2310					2310		SY	TEMPORARY EROSION MATTING	653.20				
					20					20		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
					60					60		CY	VEHICLE TRACKING PAD	653.35				
					4					4		EACH	FILTER BAG	653.45				
					1660					1660		LF	PROJECT DEMARCATION FENCE	653.55				
					2					2		SF	TRAFFIC SIGNS, TYPE A	675.20				
					75					75		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
					2					2		EACH	REMOVING SIGNS	675.50				
					2					2		EACH	ERECTING SALVAGED SIGNS	675.60				
					1					1		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
							200	300		500		CY	SPECIAL PROVISION (STONE FILL, CULVERT LINING)	900.608				
							1			1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM) (VT 58 - BRIDGE NO. 6)	900.645				
								1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM) (VT 58 - BRIDGE NO. 7)	900.645				
					1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (VT 58 - BRIDGE NO. 6)	900.645				
					1					1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (VT 58 - BRIDGE NO. 7)	900.645				
					2					2		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
					2					2		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
					810					810		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				
					15					15		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683				

NOTE: FOR DETAILED BREAKDOWN OF QUANTITIES BETWEEN BR6 AND BR7 SEE BR6 AND BR7 QUANTITY SHEETS

PROJECT NAME: IRASBURG  
PROJECT NUMBER: STP CULV(30)

FILE NAME: zllc266frm.dgn  
PROJECT LEADER: M. CHENETTE  
DESIGNED BY: J. HUNGERFORD  
QUANTITY SHEET 2

PLOT DATE: 10/21/2014  
DRAWN BY: L. BUXTON  
CHECKED BY: M. CHENETTE  
SHEET 6 OF 55

