

BR6 QUANTITY SHEET I

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL	BRIDGE NO. 6	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (VT 58 - BRIDGE NO. 6)	201.10				
							680				680		CY	COMMON EXCAVATION	203.15				
									600		600		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							0.5				0.5		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									1620		1620		CY	STRUCTURE EXCAVATION	204.25				
									870		870		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
							340				340		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
							500				500		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
							0.5				0.5		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								5			5		GAL	WATER REPELLENT, SILANE	514.10				
								220			220		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
								1			1		EACH	REMOVAL OF STRUCTURE (96" X 90' CGMP)	529.15				
								1			1		LS	PRECAST CONCRETE STRUCTURE (20'-0" X 8'-0" X 66'-6" BOX)	540.10				
							0.5				0.5		MGAL	DUST CONTROL WITH WATER	609.10				
							0.5				0.5		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
									100		100		CY	STONE FILL, TYPE III	613.12				
							638				638		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205				
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							625				625		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
									170		170		TON	CRUSHED STONE BEDDING	629.54				
							10				10		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							50				50		HR	FLAGGERS	630.15				
										0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
										0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							0.5				0.5		LS	MOBILIZATION/DEMOBILIZATION	635.11				
							640				640		LF	DURABLE 4 INCH WHITE LINE	646.400				
							640				640		LF	DURABLE 4 INCH YELLOW LINE	646.410				
									310		310		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
									100		100		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								30			30		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							30				30		LB	SEED	651.15				
							200				200		LB	FERTILIZER	651.18				
							1				1		TON	AGRICULTURAL LIMESTONE	651.20				
							1				1		TON	HAY MULCH	651.25				
							130				130		CY	TOPSOIL	651.35				
							100				100		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN (VT 58 - BRIDGE NO. 6)	652.10				
								40			40		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (VT 58 - BRIDGE NO. 6)	652.30				

PROJECT NAME: IRASBURG	
PROJECT NUMBER: STP CULV(30)	
FILE NAME: zllc266frm.dgn	PLOT DATE: 9/26/2014
PROJECT LEADER: M. CHENETTE	DRAWN BY: L. BUXTON
DESIGNED BY: J. HUNGERFORD	CHECKED BY: M. CHENETTE
BR6 QUANTITY SHEET I	SHEET 7 OF 55

