

BR7 QUANTITY SHEET I

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL ITEMS	BRIDGE NO. 7	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							1				1		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS (VT 58 - BRIDGE NO. 7)	201.10				
							580				580		CY	COMMON EXCAVATION	203.15				
									540		540		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27				
							0.5				0.5		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22				
									960		960		CY	STRUCTURE EXCAVATION	204.25				
									330		330		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				
									1		1		LS	COFFERDAM (OUTLET, STA. 1+85.00)	208.40				
							340				340		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
							440				440		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
							0.5				0.5		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
									5		5		GAL	WATER REPELLENT, SILANE	514.10				
									200		200		SY	SHEET MEMBRANE WATERPROOFING, TORCH APPLIED	519.20				
									1		1		EACH	REMOVAL OF STRUCTURE (96" X 85' CGMP)	529.15				
									1		1		LS	PRECAST CONCRETE STRUCTURE (20'-0" X 10'-0" X 56'-0" BOX)	540.10				
							0.5				0.5		MGAL	DUST CONTROL WITH WATER	609.10				
							0.5				0.5		TON	DUST AND ICE CONTROL WITH CALCIUM CHLORIDE	609.15				
									410		410		CY	STONE FILL, TYPE III	613.12				
									210		210		CY	RIPRAP, HEAVY TYPE	613.15				
							263				263		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
							150				150		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED	621.21				
							50				50		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED/NESTED	621.216				
							4				4		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
							438				438		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
									230		230		TON	CRUSHED STONE BEDDING	629.54				
							10				10		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
							50				50		HR	FLAGGERS	630.15				
										0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
										0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
										1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
							0.5				0.5		LS	MOBILIZATION/DEMobilIZATION	635.11				
							590				590		LF	DURABLE 4 INCH WHITE LINE	646.400				
							590				590		LF	DURABLE 4 INCH YELLOW LINE	646.410				
									440		440		SY	GEOTEXTILE FOR ROADBED SEPARATOR	649.11				
									570		570		SY	GEOTEXTILE UNDER STONE FILL	649.31				
								30			30		SY	GEOTEXTILE FOR SILT FENCE	649.51				
							10				10		LB	SEED	651.15				
							70				70		LB	FERTILIZER	651.18				
							1				1		TON	AGRICULTURAL LIMESTONE	651.20				
							1				1		TON	HAY MULCH	651.25				
							50				50		CY	TOPSOIL	651.35				

PROJECT NAME: IRASBURG
PROJECT NUMBER: STP CULV(30)

FILE NAME: zllc266frm.dgn
PROJECT LEADER: M. CHENETTE
DESIGNED BY: J. HUNGERFORD
BR7 QUANTITY SHEET I

PLOT DATE: 9/26/2014
DRAWN BY: L. BUXTON
CHECKED BY: M. CHENETTE
SHEET 9 OF 55

