

## BR7 QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES			
							ROADWAY	EROSION CONTROL ITEMS -	BRIDGE NO. 7	FULL C.E. ITEMS	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
							510				510		SY	GRUBBING MATERIAL	651.40				
								1			1		LS	EPSC PLAN (VT 58 - BRIDGE NO. 7)	652.10				
								40			40		HR	MONITORING EPSC PLAN	652.20				
								1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (VT 58 - BRIDGE NO. 7)	652.30				
								370			370		SY	TEMPORARY EROSION MATTING	653.20				
								10			10		CY	TEMPORARY STONE CHECK DAM, TYPE I	653.25				
								30			30		CY	VEHICLE TRACKING PAD	653.35				
								2			2		EACH	FILTER BAG	653.45				
								750			750		LF	PROJECT DEMARCATION FENCE	653.55				
							1				1		SF	TRAFFIC SIGNS, TYPE A	675.20				
							45				45		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
							2				2		EACH	REMOVING SIGNS	675.50				
							2				2		EACH	ERECTING SALVAGED SIGNS	675.60				
							0.5				0.5		LU	PRICE ADJUSTMENT, FUEL (N.A.B.I.)	690.50				
									300		300		CY	SPECIAL PROVISION (STONE FILL, CULVERT LINING)	900.608				
									1		1		LS	SPECIAL PROVISION (TEMPORARY RELOCATION OF STREAM) (VT 58 - BRIDGE NO. 7)	900.645				
											1		LS	SPECIAL PROVISION (TRAFFIC CONTROL, ALL-INCLUSIVE) (VT-58 - BRIDGE NO. 7)	900.645				
											1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(N.A.B.I.)	900.650				
											1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(N.A.B.I.)	900.650				
							380				380		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				
							7				7		CWT	SPECIAL PROVISION (EMULSIFIED ASPHALT)(RS-1H OR CRS-1H)	900.683				

PROJECT NAME: IRASBURG  
 PROJECT NUMBER: STP CULV(30)  
 FILE NAME: zllc266frm.dgn  
 PROJECT LEADER: M. CHENETTE  
 DESIGNED BY: J. HUNGERFORD  
 BR7 QUANTITY SHEET 2

PLOT DATE: 9/26/2014  
 DRAWN BY: L. BUXTON  
 CHECKED BY: M. CHENETTE  
 SHEET 10 OF 55

