


**LEGEND**



VEHICLE TRACKING PAD

ITEM 653.55 PROJECT DEMARCATIION FENCE  
 STA. 23+30.00 - 27+43.83, RT.  
 STA. 23+08.16 - 27+56.74, LT.  
 ITEM 649.51 GEOTEXTILE FOR SILT FENCE  
 SEE LOCATIONS, THIS SHEET.

**PLAN**  
 SCALE: 1" = 20'-0"  
 0 20 40



**NOTES:**

1. THE CONTRACTOR IS RESPONSIBLE FOR DEVELOPING A TEMPORARY STREAM DIVERSION PLAN. THE PLAN SHALL INCLUDE EROSION CONTROL MEASURES AS NECESSARY TO PREVENT AND CONTROL SEDIMENT DISCHARGE. SEE SPECIAL PROVISION 900.645 (TEMPORARY RELOCATION OF STREAM).
2. DEWATERING ACTIVITIES: ANY FILTER BAG OR DEWATERING ENCLOSURE FOR DISCHARGE OF DEWATERING ACTIVITIES SHALL BE LOCATED A MINIMUM OF 50 FEET FROM THE STREAM UNLESS APPROVED BY THE ENGINEER. THE FILTERING AREA SHALL BE LOCATED WITHIN THE EXISTING RIGHT-OF-WAY AND IF NECESSARY MAY BE LOCATED WITHIN A CLOSED PORTION OF THE EXISTING ROADWAY AND/OR SHOULDER.

PROJECT NAME: IRASBURG  
 PROJECT NUMBER: STP CULV(30)

FILE NAME: zllc266bdr\_EPSC\_br6.dgn  
 PROJECT LEADER: M. CHENETTE  
 DESIGNED BY: J. HUNGERFORD  
 EPSC CONST. SITE PLAN - ECPI - BR6

PLOT DATE: 9/26/2014  
 DRAWN BY: L. BUXTON  
 CHECKED BY: M. CHENETTE  
 SHEET 28 OF 55

