



Vermont Agency of Transportation
RECEIVED
 ON: April 30, 2015
 and Checked for
CONFORMANCE
 BY: Mark Sargent DATE: 5/7/2015

B1 - BILL OF MATERIALS / EMBEDS		QTY	UM	COMMENTS
CSI ID#	DESCRIPTION			
CT-00005	C			
EM-0005A	1'			
EM-00010	D			
EM-00014	D			
EM-00033	3'			
EM-00125	B			
RM-00013	R			
RM-00015	R			
RM-00017	R			
MX-FA5000SC30	M			
EM-00022	D			
RM-00013	R			
MX-FA5000SC30	M			
CT-00005	C			
EM-00018	D			
RM-00013	R	186	LB	
MX-FA5000SC30	M	1.9	CY	

B1 Rebar Schedule			
MK	QTY	LENGTH	
401 #4	18	11' - 6"	
402 #4	142	5' - 3"	
501 #5	27	26' - 1"	
502 #5	14	21' - 6"	
601 #6	27	21' - 6"	

B1 BW Rebar Schedule			
MK	QTY	LENGTH	
403 #4	2	19' - 8"	

B1 HW Rebar Schedule			
MK	QTY	LENGTH	
404 #4	30	4' - 11"	
405 #4	6	21' - 10"	

Rev.	Date	DESCRIPTION	By
5			
4			
3			
2			
1			
REVISIONS			

<p>Concrete Systems Inc. 9 Commercial St., Hudson, NH, 03051 Phone 603-889-4163 Fax 603-889-2417</p>	<p>STATE AGENCY</p>	<p>J A MCDONALD, INC. VT/AOT BRIDGE - STEEL CULVERT REPLACEMENT BRIDGE #7, VT ROUTE 58, IRASBURG, VT</p>
	<p>Drawn By R. YEAGER</p> <p>Concrete Cu. Yd. 16.78</p> <p>Approved By</p>	<p>Date 16MAR2015</p> <p>Weight in Tons 33.99</p> <p>Date</p>
<p>SHOP DRAWING - B1</p> <p>Drawing No. C22283-L02-B1</p>		<p>REV 0</p> <p>SHEET 1 OF 9</p>