

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
		ROADWAY (BRIDGE 96)	EROSION CONTROL (BRIDGE 96)	BRIDGE NO. 96	FULL C.E. ITEMS (BRIDGE 96)	ROADWAY (BRIDGE 98)	EROSION CONTROL (BRIDGE 98)	BRIDGE NO. 98	FULL C.E. ITEMS (BRIDGE 98)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
		0.5				0.5				1		LS	PUBLIC RELATIONS OFFICER	641.12				
		90				30				120		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17				
		620				528				1148		LF	4 INCH WHITE LINE	646.20				
		700				470				1170		LF	4 INCH YELLOW LINE	646.21				
		28				16				44		LF	24 INCH STOP BAR	646.26				
		4				4				8		EACH	LETTER OR SYMBOL	646.30				
				310				1950		2260		SY	GEOTEXTILE UNDER STONE FILL	649.31				
			110				80			190		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WRE REINFORCED	649.515				
			20				20			40		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
			10				2.5			12.5		LB	SEED	651.15				
			50				20			70		LB	FERTILIZER	651.18				
			0.2				0.1			0.3		TON	AGRICULTURAL LIMESTONE	651.20				
			0.2				0.1			0.3		TON	HAY MULCH	651.25				
			10				20			30		CY	TOPSOIL	651.35				
			25				30			55		SY	GRUBBING MATERIAL	651.40				
			1							1		LS	EPSC PLAN (BRIDGE 96)	652.10				
							1			1		LS	EPSC PLAN (BRIDGE 98)	652.10				
			20							20		HR	MONITORING EPSC PLAN (BRIDGE 96)	652.20				
							10			10		HR	MONITORING EPSC PLAN (BRIDGE 98)	652.20				
			1							1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BRIDGE 96)	652.30				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BRIDGE 98)	652.30				
			180				60			240		SY	TEMPORARY EROSION MATTING	653.20				
			15				15			30		CY	VEHICLE TRACKING PAD	653.35				
			1				1			2		EACH	FILTER BAG	653.45				
			490				450			940		LF	PROJECT DEMARCATION FENCE	653.55				
						8.5				8.5		SF	TRAFFIC SIGNS, TYPE A	675.20				
						15				15		LF	SQUARE TUBE SIGN POST AND ANCHOR	675.341				
				30				150		180		CY	SPECIAL PROVISION (COARSE AGGREGATE BACKFILL)	900.608				
				440				120		560		CY	SPECIAL PROVISION (GRANULAR BACKFILL FOR STRUCTURES)	900.608				
								15		15		CY	SPECIAL PROVISION (STONE FILL, STREAM BED MATERIAL)	900.608				
		1								1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(BRIDGE 96)(N.A.B.I.)	900.650				
						1				1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(BRIDGE 98)(N.A.B.I.)	900.650				
		1								1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(BRIDGE 96)(N.A.B.I.)	900.650				
						1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(BRIDGE 98)(N.A.B.I.)	900.650				
		1								1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(BRIDGE 96)(N.A.B.I.)	900.650				
						1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(BRIDGE 98)(N.A.B.I.)	900.650				
		250				280				530		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: HUBBARDTON
 PROJECT NUMBER: ER STP 0161(26) & ER STP 0161(27)
 FILE NAME: z11c288-290quantity.dgn PLOT DATE: 07/26/2012
 PROJECT LEADER: M.A. COLGAN DRAWN BY: E.A. FIALA
 DESIGNED BY: E.A. FIALA CHECKED BY: S. FARNSWORTH
 QUANTITY SHEET #2 SHEET 4 OF 70

