

# QUANTITY SHEET 1

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY (BRIDGE 96)	EROSION CONTROL (BRIDGE 96)	BRIDGE NO. 96	FULL C.E. ITEMS (BRIDGE 96)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						0.5				0.5		LS	CLEARING AND GRUBBING, INCLUDING INDIVIDUAL TREES AND STUMPS	201.10				
						410				410		CY	COMMON EXCAVATION	203.15				
								540		540		CY	UNCLASSIFIED CHANNEL EXCAVATION	203.27		410	CY	FILL AVAILABLE
						1				1		CY	TRENCH EXCAVATION OF EARTH, EXPLORATORY (N.A.B.I.)	204.22		540	CY	COMMON EXCAVATION
								200		200		CY	GRANULAR BACKFILL FOR STRUCTURES	204.30				UNCLASSIFIED CHANNEL EXCAVATION
								700		700		CY	COFFERDAM EXCAVATION, EARTH	208.30				UNDERDRAIN EXCAVATION
								80		80		CY	COFFERDAM EXCAVATION, ROCK	208.35				STRUCTURE EXCAVATION
								1		1		LS	COFFERDAM (ABUTMENT NO. 1)	208.40		1	CY	TRENCH EXCAVATION OF EARTH
								1		1		LS	COFFERDAM (ABUTMENT NO. 2)	208.40		4	CY	ROUNDING
						220				220		SY	COLD PLANING, BITUMINOUS PAVEMENT	210.10				
						470				470		CY	SUBBASE OF DENSE GRADED CRUSHED STONE	301.35				
						100				100		CWT	EMULSIFIED ASPHALT	404.65				
						1				1		LU	PRICE ADJUSTMENT, ASPHALT CEMENT (N.A.B.I.)	406.50				
								12		12		GAL	WATER REPELLENT, SILANE	514.10				
								11		11		LF	JOINT SEALER, HOT POURED	524.11				
								70.4		70.4		LF	BRIDGE RAILING, GALVANIZED 2 RAIL BOX BEAM	525.33				
								1		1		EACH	REMOVAL OF STRUCTURE (THREE 60" X 60' HDPE)	529.15				
								1		1		LS	PRECAST CONCRETE STRUCTURE (32'-0" X 10'-0" X 40'-0" FRAME OR ARCH)	540.10				
						5				5		CY	STONE FILL, TYPE I	613.10				
								120		120		CY	STONE FILL, TYPE II	613.11				
						145				145		LF	CAST-IN-PLACE CONCRETE CURB, TYPE B	616.28				
						14.5				14.5		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20				
						1				1		EACH	MANUFACTURED TERMINAL SECTION, FLARED	621.50				
						2				2		EACH	MANUFACTURED TERMINAL SECTION, TANGENT	621.51				
						1				1		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60				
						4				4		EACH	GUARDRAIL APPROACH SECTION, GALVANIZED 2 RAIL BOX BEAM	621.72				
						241				241		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80				
						63				63		LF	TEMPORARY TRAFFIC BARRIER	621.90				
						300				300		HR	UNIFORMED TRAFFIC OFFICERS	630.10				
						720				720		HR	FLAGGERS	630.15				
									0.5	0.5		LS	FIELD OFFICE, ENGINEERS	631.10				
									0.5	0.5		LS	TESTING EQUIPMENT, BITUMINOUS	631.17				
									1500	1500		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26				
						0.5				0.5		LS	MOBILIZATION/DEMOBILIZATION	635.11				
						1				1		LS	TRAFFIC CONTROL (BRIDGE 96)	641.10				
						0.5				0.5		LS	PUBLIC RELATIONS OFFICER	641.12				
						90				90		DAY	PORTABLE CHANGEABLE MESSAGE SIGN RENTAL	641.17				
						620				620		LF	4 INCH WHITE LINE	646.20				
						700				700		LF	4 INCH YELLOW LINE	646.21				
						28				28		LF	24 INCH STOP BAR	646.26				

PROJECT NAME:	HUBBARDTON
PROJECT NUMBER:	ER STP 0161(26)
FILE NAME:	z11c288qs.dgn
PROJECT LEADER:	M.A. COLGAN
DESIGNED BY:	E.A. FIALA
QUANTITY SHEET #1	
PLOT DATE:	07/13/2012
DRAWN BY:	E.A. FIALA
CHECKED BY:	S. FARNSWORTH
SHEET	11 OF 70

