

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
						ROADWAY (BRIDGE 96)	EROSION CONTROL (BRIDGE 96)	BRIDGE NO. 96	FULL C.E. ITEMS (BRIDGE 96)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
						4				4		EACH	LETTER OR SYMBOL	646.30				
								310		310		SY	GEOTEXTILE UNDER STONE FILL	649.31				
							110			110		SY	GEOTEXTILE FOR SILT FENCE, WOVEN WIRE REINFORCED	649.515				
							20			20		SY	GEOTEXTILE FOR FILTER CURTAIN	649.61				
							10			10		LB	SEED	651.15				
							50			50		LB	FERTILIZER	651.18				
							0.2			0.2		TON	AGRICULTURAL LIMESTONE	651.20				
							0.2			0.2		TON	HAY MULCH	651.25				
							10			10		CY	TOPSOIL	651.35				
							25			25		SY	GRUBBING MATERIAL	651.40				
							1			1		LS	EPSC PLAN (BRIDGE 96)	652.10				
							20			20		HR	MONITORING EPSC PLAN (BRIDGE 96)	652.20				
							1			1		LU	MAINTENANCE OF EPSC PLAN (N.A.B.I.) (BRIDGE 96)	652.30				
							180			180		SY	TEMPORARY EROSION MATTING	653.20				
							15			15		CY	VEHICLE TRACKING PAD	653.35				
							1			1		EACH	FILTER BAG	653.45				
							490			490		LF	PROJECT DEMARCATION FENCE	653.55				
								30		30		CY	SPECIAL PROVISION (COARSE AGGREGATE BACKFILL)	900.608				
								440		440		CY	SPECIAL PROVISION (GRANULAR BACKFILL FOR STRUCTURES)	900.608				
						1				1		LU	SPECIAL PROVISION (INCENTIVE/DISINCENTIVE)(BRIDGE 96)(N.A.B.I.)	900.650				
						1				1		LU	SPECIAL PROVISION (MAT DENSITY PAY ADJUSTMENT, SMALL QUANTITY)(BRIDGE 96)(N.A.B.I.)	900.650				
						1				1		LU	SPECIAL PROVISION (MIXTURE PAY ADJUSTMENT)(BRIDGE 96)(N.A.B.I.)	900.650				
						250				250		TON	SPECIAL PROVISION (BITUMINOUS CONCRETE PAVEMENT, SMALL QUANTITY)	900.680				

PROJECT NAME: HUBBARDTON
 PROJECT NUMBER: ER STP 0161(26)
 FILE NAME: z11c288qs.dgn
 PROJECT LEADER: M.A. COLGAN
 DESIGNED BY: E.A. FIALA
 QUANTITY SHEET #2
 PLOT DATE: 07/26/2012
 DRAWN BY: E.A. FIALA
 CHECKED BY: S. FARNSWORTH
 SHEET 12 OF 70

