

QUANTITY SHEET 2

SUMMARY OF ESTIMATED QUANTITIES										TOTALS		DESCRIPTIONS				DETAILED SUMMARY OF QUANTITIES		
		ROADWAY	NO FEDERAL PART.	NO FEDERAL/ STATE PART.	TRAINING	RAILROAD	BRIDGE	FULL C.E. ITEMS	ROADWAY SRIN(20)	GRAND TOTAL	FINAL	UNIT	ITEMS	ITEM NUMBER	ROUND	QUANTITIES	UNIT	ITEMS
		28								28		EACH	YIELDING MARKER POSTS	619.17	EST.			SEED
		1425								1425		LF	STEEL BEAM GUARDRAIL, GALVANIZED	621.20	25.5	2	LB	DITCH CLEANING
		2400								2400		LF	STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.205	30	157	LB	TURF ESTABLISHMENT
		37.5								37.5		LF	HD STEEL BEAM GUARDRAIL, GALVANIZED W/8 FEET POSTS	621.215	5	0.8	LB	LYNDON U.S. ROUTE 5 CENTER ISLAND STA. 149+35 - 150+85, LT
		21								21		EACH	ANCHOR FOR STEEL BEAM RAIL	621.60	-	3.2	LB	LYNDON U.S. ROUTE 5 GROVE ST. PAVEMENT REMOVAL SAFE ROUTES TO SCHOOL SRIN(20)
		3725								3725		LF	REMOVAL AND DISPOSAL OF GUARDRAIL	621.80	3.5	0.2	LB	ST. JOHNSBURY
		248								248		EACH	ADJUST ELEVATION OF VALVE BOX	629.20	-	0.8	LB	U.S. ROUTE 2 STA. 153+23, LT
		1700								1700		HR	UNIFORMED TRAFFIC OFFICERS	630.10	EST.	6	LB	U.S. ROUTE 2 BARKER AVE. PAVEMENT REMOVAL
		17300								17300		HR	FLAGGERS	630.15	EST.	170	LB	ROUNDING
								1		1		LS	FIELD OFFICE, ENGINEERS	631.10	-			TOTAL
								1		1		LS	TESTING EQUIPMENT, CONCRETE	631.16	-			
								1		1		LS	TESTING EQUIPMENT, BITUMINOUS	631.17	-			
								3000		3000		DL	FIELD OFFICE TELEPHONE (N.A.B.I.)	631.26	-			
					1040					1040		HR	EMPLOYEE TRAINEESHIP (N.A.B.I.)	634.10	EST.			
		1								1		LS	MOBILIZATION/DEMobilIZATION	635.11	-			
		1								1		LS	TRAFFIC CONTROL	641.10	-			
		6								6		EACH	PORTABLE CHANGEABLE MESSAGE SIGN	641.15	-			
		4								4		EACH	RAILROAD CROSSING SYMBOL	646.32	-			
		79400								79400		LF	DURABLE 4 INCH WHITE LINE, TYPE A TAPE	646.4011	816			
		74700								74700		LF	DURABLE 4 INCH YELLOW LINE, TYPE A TAPE	646.4111	750			
		1750								1750		LF	DURABLE 8 INCH WHITE LINE, TYPE A TAPE	646.4411	37			
		895								895		LF	DURABLE 8 INCH YELLOW LINE, TYPE A TAPE	646.4511	10			
		1570								1570		LF	DURABLE 24 INCH STOP BAR, TYPE A TAPE	646.4811	15			
		570								570		EACH	DURABLE LETTER OR SYMBOL, TYPE D TAPE	646.4914	-			
		15								15		LF	DURABLE CROSSWALK MARKING	646.500	1			
		4910								4910		LF	DURABLE CROSSWALK MARKING, TYPE A TAPE	646.5011	54			
		7								7		LF	DURABLE RAILROAD CROSSING SYMBOL, TYPE D TAPE	646.5114	-			
		158700								158700		LF	TEMPORARY 4 INCH WHITE LINE, PAINT	646.602	1532			
		148400								148400		LF	TEMPORARY 4 INCH YELLOW LINE, PAINT	646.612	1492			
		3460								3460		LF	TEMPORARY 8 INCH WHITE LINE, PAINT	646.642	34			
		1790								1790		LF	TEMPORARY 8 INCH YELLOW LINE, PAINT	646.652	20			
		3140								3140		LF	TEMPORARY 24 INCH STOP BAR, PAINT	646.682	30			
		1036								1036		EACH	TEMPORARY LETTER OR SYMBOL, PAINT	646.692	-			
		9750								9750		LF	TEMPORARY CROSSWALK MARKING, PAINT	646.702	130			
		14								14		EACH	TEMPORARY RAILROAD CROSSING SYMBOL, PAINT	646.712	-			
		4370								4370		EACH	LINE STRIPING TARGETS	646.76	53			
		600								600		SY	GEOTEXTILE UNDER STONE FILL	649.31	13			
		170								170		LB	SEED	651.15	6			
		910								910		LB	FERTILIZER	651.18	EST.			
		4								4		TON	AGRICULTURAL LIMESTONE	651.20	EST.			

PROJECT NAME: ST. JOHNSBURY-LYNDON
 PROJECT NUMBER: STP 2936(I)
 FILE NAME: ... \Plot+files\pllc308qs02.dgn PLOT DATE: 5/5/2014
 PROJECT LEADER: G. EDWARDS DRAWN BY: D. DRAPER
 DESIGNED BY: D. DRAPER CHECKED BY: J. LITTLE
 SHEET 9 OF 250

