

# ITEM DETAIL SUMMARY SHEET 1

LOCATION			GUARDRAIL						MISCELLANEOUS											REMARKS	
BEGIN MILE STA.	END MILE STA.	POS.	621.20	621.205	621.215	621.60	621.80	900.640	203.15	203.30	301.28	402.13	604.40	604.412	604.415	604.418	613.10	616.20	616.21		616.28
			S.B. G.R. GALV.	S.B. G.R. GALV. 8' POST	HD S.B. G.R. GALV. 8' POST	ANCHOR FOR S.B. RAIL	REMOVAL & DISPOSAL OF GUARDRAIL	ALUMINUM APPROACH RAILING	COMMON EXCAVATION	EARTH BORROW	SUBBASE OF CRUSHED GRAV. FINE GRADED	AGGREGATE SHOULDERS, RAP	CHAN ELEV OF DI, CB OR MH	REHAB DI, CB, OR MH, CLASS I	REHAB DI, CB, OR MH, CLASS II	REHAB DI, CB, OR MH, CLASS III	STONE FILL, TYPE I	GRANITE SLOPE EDGING	VERTICAL GRANITE CURB		C-I-P CONC. CURB, TYPE B
			LF	LF	LF	EACH	LF	LF	CY	CY	TON	TON	EACH	EACH	EACH	EACH	CY	LF	LF	LF	
TOWN OF ST. JOHNSBURY U.S. ROUTE 2																					
141+50.04	146+85.0	LT&RT										32	44	74	10	9					
143+60.0	146+85.0	RT	329			2	317			50											
148+54		LT							3.9		3.7								12		
148+54		LT							3.9		3.3						16				
148+54		RT							4.3		4.0								11.5		
153+23		RT							6.9		11.7										
153+23		LT							3.9		8.9								28		
160+68		RT							16.7		18.6								42		
160+95	161+17	RT							3.2												
161+08		RT							9.2		10.3								54		
161+24	162+31	RT							25.1		39.4										
163+27		RT							0.8		0.9										
163+50		RT							0.9		0.9										
163+88		RT							1.0		1.1										
163+88		LT							1.0		1.1										
172+92		RT							6.1		5.8										
172+92		LT							0.8		0.7										
176+17		LT							0.9		0.9										
176+17		RT							1.9		1.8										
179+76		RT							0.7		0.7										
180+29		RT							0.4		0.4										
180+33		LT							6.5		6.1									11.0	
181+00		LT							1.7		1.6										
181+40		LT							2.5		2.5										
182+61		LT							4.2		4.0									9.5	
182+65		RT							0.8		0.7										
183+04		RT							3.2		3.0									5.0	
185+15	185+31	LT																			
185+24		RT							3.2		3.2									10.0	
185+26		LT							2.4		2.3									5.5	
185+66		LT							2.7		2.6										
187+75		LT							2.4		2.3									10.0	
188+09		LT							1.9		1.8										
SHEET SUBTOTALS:			329			2	317		123.1	50	144.3	32	44	74	10	9		16	147.5		51

**ITEM  
DETAIL  
SUMMARY  
SHEET #1**

PROJECT NAME: ST. JOHNSBURY - LYNDON	
PROJECT NUMBER: STP 2936(1)	
FILE NAME: p11c308.dgn	PLOT DATE: 5/5/2014
PROJECT LEADER: G. EDWARDS	DRAWN BY: D. DRAPER
DESIGNED BY: D. DRAPER	CHECKED BY: J. LITTLE
	SHEET 12 OF 250