

ITEM DETAIL SUMMARY SHEET 12

LOCATION			MISCELLANEOUS																REMARKS	
BEGIN MILE STA.	END MILE STA.	POS.	616.35	616.40	616.41	616.47	618.10	618.11	618.30	619.17	649.31	653.20	676.10	900.620	900.620	900.620	900.620	900.620		
			TREATED TIMBER CURB	REMOVING & RESETTING CURB	REMOVAL OF EXISTING CURB	BIT. CONC. GUTTERS & ISLANDS	PORTLAND CEMENT CONC. S.W., 5 INCH	PORTLAND CEMENT CONC. S.W., 8 INCH	DETECTABLE WARNING SURFACE	YIELDING MARKER POSTS	GEOTEXTILE UNDER STONE FILL	TEMPORARY EROSION MATTING	DELINEATOR WITH STEEL POST	S.P. (PARKING METER)	S.P. (PARKING METER POST)	S.P. (REMOVE & RESET PRK. MTR.)	S.P. (REMOVE PRK. MTR.)	S.P. (REMOVE PRK. MTR. POST)		
			LF	LF	LF	TON	SY	SY	SF	EACH	SY	SY	EACH	EACH	EACH	EACH	EACH	EACH		
TOWN OF LYNDON U.S. ROUTE 5 (CONT.)																				
151+75		RT					3		8										CONSTRUCT SIDEWALK RAMP, TYPE 1	
151+89		LT			17		13		8										CONSTRUCT SIDEWALK RAMP, TYPE 5	
152+28		LT			5.0		3		8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
152+56		RT			25.5		7		8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
153+95		RT					5		12										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
153+99		LT			18.5		10		8										CONSTRUCT SIDEWALK RAMP, TYPE 6	
154+68		RT					4		10										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
155+63		LT					2		8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
155+63		RT			5.0		3		8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
156+20		LT					3		8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
158+04		RT					9		16										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
158+06		LT			6.0		9		8										CONSTRUCT SIDEWALK RAMP, TYPE 6	
158+25		LT			5.0		14		8										CONSTRUCT SIDEWALK RAMP, TYPE 5	
159+00		LT					3		8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
159+44		LT					7		6										CONSTRUCT SIDEWALK RAMP, TYPE 1	
159+93		RT					5		8										CONSTRUCT SIDEWALK RAMP, TYPE 2	
159+93		LT					4		8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
161+45	161+64	RT				0.9													CONSTRUCT BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56	
161+50		LT				0.2													CONSTRUCT PERPENDICULAR BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56	
162+65		LT				0.2													CONSTRUCT PERPENDICULAR BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56	
163+15		RT				0.3													CONSTRUCT PERPENDICULAR BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56	
163+40		RT					2		6										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
163+82		RT					5		12										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
164+02		RT				0.2													CONSTRUCT PERPENDICULAR BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56	
171+42		RT					6		12										CONSTRUCT SIDEWALK RAMP, TYPE 2	
171+53		LT			8.0		5		10										CONSTRUCT SIDEWALK RAMP, TYPE 2	
171+75		RT									196								REMOVE GROVE STREET EXISTING PAVEMENT. SEE SHEET 127.	
176+72		LT					3		10										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
186+27		LT					5		6										CONSTRUCT SIDEWALK RAMP, TYPE 1	
186+75		RT					3		8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE	
187+62.5	188+12.5	LT									50	2							INSTALL ANCHOR @ STA. 187+62.5 & STA. 188+12.5.	
189+53.0	189+90.5	LT									50	2							INSTALL ANCHOR @ STA. 189+53.0 & STA. 189+90.5.	
189+97.5	190+97.5	RT									25	1							INSTALL ANCHOR @ STA. 189+97.5; CONNECT TO EXISTING BRIDGE RAIL @ STA. 190+97.5	
SHEET SUBTOTALS:					90.0	1.8	133		212		321	5							ITEM DETAIL SUMMARY SHEET #12	PROJECT NAME: ST. JOHNSBURY - LYNDON PROJECT NUMBER: STP 2936(1) FILE NAME: pllc308.dgn PROJECT LEADER: G. EDWARDS DESIGNED BY: D. DRAPER PLOT DATE: 5/5/2014 DRAWN BY: D. DRAPER CHECKED BY: J. LITTLE SHEET 23 OF 250