

THINNING AND TRIMMING FOR SIGNS

STA. 154+04, LT  
STA. 155+58, LT  
SEE SHEET 24 (TYP.)

CHANGING ELEVATION OF Dis, CBs OR MHs  
SEE SHEET 27

REHAB.  
Dis, CBs OR MHs, CLASS I, II OR III  
SEE SHEETS 27-28

CHANGING ELEVATION OF SEWER MANHOLES  
SEE SHEET 28

CAST-IN-PLACE CONCRETE CURB, TYPE B

STA. 155+63, RT  
STA. 158+06, LT  
STA. 158+25, LT

REMOVAL OF EXISTING CURB

STA. 155+63, RT  
STA. 158+06, LT  
STA. 158+25, LT

PORTLAND CEMENT  
CONCRETE SIDEWALK, 5 INCH

STA. 154+68, RT  
STA. 155+63, RT  
STA. 155+63, LT  
STA. 156+20, LT  
STA. 158+04, RT  
STA. 158+06, LT  
STA. 158+25, LT  
STA. 159+00, LT  
STA. 159+44, LT  
STA. 159+93, RT  
STA. 159+93, LT

DETECTABLE WARNING SURFACE

STA. 154+68, RT  
STA. 155+63, RT  
STA. 155+63, LT  
STA. 156+20, LT  
STA. 158+04, RT  
STA. 158+06, LT  
STA. 158+25, LT  
STA. 159+00, LT  
STA. 159+44, LT  
STA. 159+93, RT  
STA. 159+93, LT

ADJUST ELEVATION OF VALVE BOX  
SEE SHEETS 28-29

DURABLE & TEMPORARY 4 INCH WHITE LINE

(ALL LINES WILL INCLUDE EDGE LINE BREAKS  
AND RADIUS FOR SIDE ROADS)  
STA. 154+00 TO 158+03, SOLID LT (PARKING SPACES & DIAGONALS)  
SEE SHEETS 55 TO 56 (TYP.)  
STA. 154+00 TO 154+52, DOTTED LT  
STA. 154+31, SOLID RT (PARKING SPACES & DIAGONALS, CHURCH ST.)  
STA. 154+61 TO 158+01, SOLID RT (PARKING SPACES & DIAGONALS)  
STA. 155+91, SOLID LT (PARKING SPACES & DIAGONALS, ELM ST.)  
STA. 158+30 TO 159+01, SOLID LT (PARKING SPACES & DIAGONALS)  
STA. 158+32, SOLID LT (PARKING SPACES & DIAGONALS, MAIN ST.)  
STA. 158+39 TO 160+00, SOLID RT  
STA. 159+22, SOLID LT (PARKING SPACES & DIAGONALS, MAPLE ST.)  
STA. 159+44 TO 160+00, SOLID LT

DURABLE & TEMPORARY 4 INCH YELLOW LINE

(ALL LINES WILL INCLUDE  $\frac{1}{2}$  BREAKS FOR SIDE ROADS & CROSSWALKS)  
STA. 154+00 TO 160+00, SOLID LT & RT  
STA. 154+31, DOUBLE SOLID RT (CHURCH ST.)  
STA. 155+91, DOUBLE SOLID LT (ELM ST.)  
STA. 159+22, DOUBLE SOLID LT (MAPLE ST.)

DURABLE & TEMPORARY 8 INCH WHITE LINE

STA. 159+76 TO 159+88, RT (HYDRANT)  
SEE SHEET 55

DURABLE & TEMPORARY 24 INCH STOP BAR

STA. 154+31, RT (CHURCH ST.)  
STA. 155+91, LT (ELM ST.)  
STA. 158+32, LT (MAIN ST.)  
STA. 159+22, LT (MAPLE ST.)

DURABLE & TEMPORARY LETTER OR SYMBOL

STA. 154+29, LT HANDICAP SYMBOL  
STA. 154+31, RT "STOP" (CHURCH ST.)  
STA. 155+91, LT "STOP" (ELM ST.)  
STA. 158+32, LT "STOP" (MAIN ST.)  
STA. 159+22, LT "STOP" (MAPLE ST.)

DURABLE CROSSWALK MARKING, TYPE A TAPE

STA. 154+31, RT (CHURCH ST.)  
STA. 155+63, LT - RT  
STA. 155+91, LT (ELM ST.)  
STA. 158+04, RT TO 158+06, LT  
STA. 158+32, LT (MAIN ST.)  
STA. 159+22, LT (MAPLE ST.)  
STA. 159+93, LT - RT  
SEE SHEET 55 (TYP.)

TEMPORARY CROSSWALK MARKING, PAINT

STA. 154+31, RT (CHURCH ST.)  
STA. 155+63, LT - RT  
STA. 155+91, LT (ELM ST.)  
STA. 158+04, RT TO 158+06, LT  
STA. 158+32, LT (MAIN ST.)  
STA. 159+22, LT (MAPLE ST.)  
STA. 159+93, LT - RT  
SEE SHEET 55 (TYP.)

REMOVING SIGNS

AS SHOWN - 24

ERECTING SALVAGED SIGNS

AS SHOWN - 6

NOT TO SCALE



**PROJECT  
LAYOUT  
SHEET #57B**

PROJECT NAME: ST JOHNSBURY - LYNDON  
PROJECT NUMBER: STP 2936(I)

FILE NAME: pllc308.dgn  
PROJECT LEADER: G. EDWARDS  
DESIGNED BY: D. DRAPER

PLOT DATE: 5/5/2014  
DRAWN BY: D. DRAPER  
CHECKED BY: J. LITTLE  
SHEET 124 OF 250