STATE OF VERMONT
AGENCY OF TRANSPORTATION

TRAFFIC SIGN SUMMARY SHEET 84

MILEMARKER, STATION, OR SIGN NUMBER	SIGN LEGEND	SIGN DIMENSIONS EA	WIDTH (in)	HEIGHT (in)	NEW & SALVAGED SIGNS "A"	"B"	SALV SIGN	SALV TIS	EXIST POST RETAIN	EXIST POST SALVAGE	NEW SIGN POSTS NO. OF POSTS	FLANGED CHANNEL lb/ft 1.12	2.0	3.0	SQUARE STEEL (in) lb/ft 1.88	1.75	2.0	2.42	2.5	3.35	ANCHOR	SLEEVE	TUBULAR ALUMINUM Ø (in) lb/ft 1.3	3.0	4.0	1.7	4.0 MOD	1.7	FOUND-ATION	TUBULAR STEEL Ø (in) lb/ft 7.6	3.0	3.5	9.0	4.0	10.8	5.0	14.6	W-SHAPE STEEL FTG. SIZE 24"	30"	WEIGHT	POST SIZE	SIGN FRAME REQUIRED	REMARKS	SIGN DETAIL DETAIL IN SHSM * BOOK	DETAIL ON SHEET NUMBER	STD. SHEET NUMBER
LYNDON ALT. VT ROUTE 122 (CONT.)																																											
44+55, RT	11'-9" / ONE LANE BRIDGE / 15 MPH	1	36	36	9.00						2							X		X	X																		WI2-2	X		
		1	36	36	9.00																																		W5-3	X		
		1	18	18	2.25																																		WI3-IP	X		
46+50, LT	SPEED LIMIT 25	1	24	30	5.00						1						X			X																		R2-1	X		
49+88, RT	JCT / VERMONT 122 / 1220 0307 0094	1	21	15	2.19						1						X			X																		M2-1 (GREEN ON WHITE)	X		
		1	30	24	5.00																																		(GREEN ON WHITE)			E-136B
		1	6	10	0.42																																		VD-700			E-138
50+75, RT	NORTH TO SOUTH / VERMONT 122 5 VERMONT 122 / TO VERMONT 114 / TO EXIT 91	1	24	12	2.00						2																			2	X								M3-1 (GREEN ON WHITE)	X		
		1	24	12	2.00																																		M4-5 (BLACK ON WHITE)	X		
		1	24	12	2.00																																		M3-3 (GREEN ON WHITE)	X		
		1	30	24	5.00																																		(GREEN ON WHITE)			E-136B
		1	24	24	4.00																																		MI-4	X		
		1	30	24	5.00																																		(GREEN ON WHITE)			E-136B
		1	21	15	2.19																																	*3	M5-1 (GREEN ON WHITE) FOR SIGN FRAME DETAIL SEE SHEET 241	X		
		1	21	15	2.19																																		M5-1 (BLACK ON WHITE)	X		
		1	24	12	2.00																																		M4-5 (GREEN ON WHITE)	X		
		1	24	12	2.00																																		M4-5 (WHITE ON BLUE)	X		
		1	30	24	5.00																																		(GREEN ON WHITE)			E-136B
		1	24	24	4.00																																		MI-1	X		
		1	21	15	2.19																																		M5-1 (GREEN ON WHITE)	X		
		1	21	15	2.19																																		M5-1 (WHITE ON BLUE)	X		
51+47, RT	BRIDGE 4 VT 122	1	6	10	0.42						1				X					X																		VD-701		238	
52+50, LT	SOUTH ALT VERMONT 122 / BRIDGE 4 VT 122	1	24	12	2.00						1						X			X																		M3-3 (GREEN ON WHITE)	X		
		1	24	12	2.00																																		M4-1a (GREEN ON WHITE)	X		
		1	30	24	5.00																																		(GREEN ON WHITE)			E-136B
		1	6	10	0.42																																		VD-701		238	
												FT	FT	FT	FT	FT	FT		EA	LB	LB	LB		LB	LB	LB	LB														
															8	45	40							221																	
TOTALS			SF 84.46	SF	EA.	SF						FT			FT 93									LB				EA. 2	LB 221					EA.	EA.	LB					

* "SHSM"-STANDARD HIGHWAY SIGNS AND MARKINGS

FINAL POST LENGTHS ARE TO BE DETERMINED IN THE FIELD. POST SIZES ARE COMPUTED BASED ON INFORMATION FURNISHED ON THE STANDARD SHEETS AND THE VTRANS "SIGN POST DESIGN GUIDELINE."

TRAFFIC SIGN SUMMARY SHEET #84

PROJECT NAME: ST JOHNSBURY - LYNDON
PROJECT NUMBER: STP 2936(I)

FILE NAME: plic308.dgn
PROJECT LEADER: G. EDWARDS
DESIGNED BY: D. DRAPER
PLOT DATE: 5/5/2014
DRAWN BY: D. DRAPER
CHECKED BY: J. LITTLE
SHEET 225 OF 250