

ITEM DETAIL SUMMARY SHEET 1																							
LOCATION			GUARDRAIL						MISCELLANEOUS											REMARKS			
BEGIN MILE STA.	END MILE STA.	POS.	621.20	621.205	621.215	621.60	621.80	900.640	203.15	203.30	301.28	402.13	604.40	604.412	604.415	604.418	613.10	616.20	616.21			616.28	
			S.B. G.R. GALV.	S.B. G.R. GALV. 8' POST	HD S.B. G.R. GALV. 8' POST	ANCHOR FOR S.B. RAIL	REMOVAL & DISPOSAL OF GUARDRAIL	ALUMINUM APPROACH RAILING	COMMON EXCAVATION	EARTH BORROW	SUBBASE OF CRUSHED GRAV. FINE GRADED	AGGREGATE SHOULDERS, RAP	CHAN ELEV OF DI, CB OR MH	REHAB DI, CB, OR MH, CLASS I	REHAB DI, CB, OR MH, CLASS II	REHAB DI, CB, OR MH, CLASS III	STONE FILL, TYPE I	GRANITE SLOPE EDGING	VERTICAL GRANITE CURB			C-I-P CONC. CURB, TYPE B	
			LF	LF	LF	EACH	LF	LF	CY	CY	TON	TON	EACH	EACH	EACH	EACH	CY	LF	LF			LF	
TOWN OF ST. JOHNSBURY U.S. ROUTE 2																							
141+50.04	148+10.72	LT&RT										32	44	74	10	9					QUANTITIES FOR USE AS DIRECTED BY THE ENGINEER, FOR STRUCTURE LOCATIONS, SEE SHEETS 27-29		
143+60.0	146+85.0	RT	329			2	317			50											INSTALL ANCHOR @ STA. 143+60.0 & STA. 146+85.0		
148+54		LT							3.9		3.7							12			CONSTRUCT SIDEWALK RAMP, TYPE 2		
148+54		LT							3.9		3.3						16				RECONSTRUCT MEDIAN ISLAND CUT THROUGH. SEE SHEET 57.		
148+54		RT							4.3		4.0							11.5			CONSTRUCT SIDEWALK RAMP, TYPE 2		
153+23		RT							6.9		11.7										CONSTRUCT SIDEWALK RAMP, TYPE 2 (PAID AS ROADWAY SRIN(20))		
153+23		LT							3.9		8.9							28			CONSTRUCT SIDEWALK RAMP, TYPE 3 (PAID AS ROADWAY SRIN(20))		
160+68		RT							16.7		18.6							42			CONSTRUCT SIDEWALK RAMP, TYPE 1 (PAID AS ROADWAY SRIN(20))		
160+95	161+17	RT							3.2												REMOVE BARKER AVENUE EXISTING PAVEMENT. SEE SHEET 64 (PAID AS ROADWAY SRIN(20)).		
161+08		RT							9.2		10.3							54			CONSTRUCT SIDEWALK RAMP, TYPE 1 (PAID AS ROADWAY SRIN(20))		
161+24	162+31	RT							25.1		39.4										CONSTRUCT SIDEWALK (5" DEPTH) STA. 161+24 TO 161+86. CONSTRUCT SIDEWALK (8" DEPTH) STA. 161+86 TO 162+31. REMOVE AND RESET CURB. SEE SHEET 58 (PAID AS ROADWAY SRIN(20)).		
163+27		RT							0.8		0.9										CONSTRUCT SIDEWALK RAMP, TYPE 1		
163+50		RT							0.9		0.9										CONSTRUCT SIDEWALK RAMP, TYPE 1		
163+88		RT							1.0		1.1										CONSTRUCT SIDEWALK RAMP, TYPE 1 (PAID AS ROADWAY SRIN(20))		
163+88		LT							1.0		1.1										CONSTRUCT SIDEWALK RAMP, TYPE 1 (PAID AS ROADWAY SRIN(20))		
172+92		RT							6.1		5.8										CONSTRUCT SIDEWALK RAMP, TYPE 2		
172+92		LT							0.8		0.7										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
176+17		LT							0.9		0.9										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
176+17		RT							1.9		1.8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
179+76		RT							0.7		0.7										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
180+29		RT							0.4		0.4										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
180+33		LT							6.5		6.1									11.0	CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
181+00		LT							1.7		1.6										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
181+40		LT							2.5		2.5										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
182+61		LT							4.2		4.0									9.5	CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
182+65		RT							0.8		0.7										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
183+04		RT							3.2		3.0									5.0	CONSTRUCT SIDEWALK RAMP, TYPE 1		
185+15	185+31	LT																			CONSTRUCT BITUMINOUS GUTTER, SEE DETAIL ON SHEET 56		
185+24		RT							3.2		3.2									10.0	CONSTRUCT SIDEWALK RAMP, TYPE 6		
185+26		LT							2.4		2.3									5.5	CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
185+66		LT							2.7		2.6										CONSTRUCT SIDEWALK RAMP, TYPE 1		
187+75		LT							2.4		2.3									10.0	CONSTRUCT SIDEWALK RAMP, TYPE 1		
188+09		LT							1.9		1.8										CONSTRUCT SIDEWALK LANDING AND INSTALL DETECTABLE WARNING SURFACE		
SHEET SUBTOTALS:			329			2	317		123.1	50	144.3	32	44	74	10	9		16	147.5	51	ITEM DETAIL SUMMARY SHEET #1	PROJECT NAME: ST. JOHNSBURY - LYNDON	
																				PROJECT NUMBER: STP 2936(1)			
																				FILE NAME: pl1c308.dgn			
																				PLOT DATE: 5/5/2014			
																				DRAWN BY: D. DRAPER			
																				CHECKED BY: J. LITTLE			
																				SHEET 12 OF 250			